

AGREEMENT FOR COST SHARING OF OFFSITE SEWER LINE

This Agreement for Cost Sharing of Offsite Sewer Line (this "Agreement") is entered into on the 9th day of December, 2025, to be effective as of the Effective Date (hereinafter defined), by and among the City of Denton, Texas (the "City") and Denton JV, a joint venture between RM Squared Denton, LLC, and Baker 345, LLC (collectively, the "Developer"). Developer and the City are sometimes collectively referred to herein as the "Parties" and individually as a "Party."

RECITALS

WHEREAS, Developer is the owner or developer of the approximately 352.71 acres of land located north of Hampton Road and east of Lovers Lane in the City and described in **Exhibit "A"**, attached hereto (the "Baker Tract"); and

WHEREAS, Developer is in the process of developing and improving the Baker Tract and, in connection with the same, must secure onsite and offsite easements for the City; and

WHEREAS, onsite and offsite easements are needed to ensure sanitary sewer line facilities are available to serve the Hickory Creek service area from the Wastewater Master Plan; and

WHEREAS, the City intends to construct Capital Improvement Project 13 - North Masch Sewer Line, a sewer line of approximately 9,114 linear feet, the approved plans of which are attached hereto as **Exhibit "B"** (the "City Sewer Line"); and

WHEREAS, the City Sewer Line will be extended to serve the Baker Tract, as shown in Exhibit "B", attached hereto, and other property not owned by Developer, including future light industrial development to the south; and

WHEREAS, subject to Section 2.1, the City intends to start procurement within six (6) months and construction within one (1) year start construction of the City Sewer Line within the Effective Date of this Agreement, in accordance with the City's Wastewater Master Plan; and

WHEREAS, to expedite the construction of the City Sewer Line, Developer has engaged Kimley-Horn & Associates, Inc. to design and provide engineering services for the City Sewer Line, and Developer has already funded costs associated with such design and engineering for the City Sewer Line; and

WHEREAS, Developer has agreed to fund Developer's proportionate share of the cost of design, easement acquisition, surveying, engineering, potholing, construction, legal fees, and all other associated costs of the City Sewer Line (the "City Sewer Line Costs"); and

WHEREAS, the estimated total cost of Developer's proportionate share is included in **Exhibit "C"**, attached hereto; and

WHEREAS, the City and Developer desire to set forth, in writing, their understandings and agreement regarding the design, construction, and installation of the City Sewer Line as more fully set forth herein; and

WHEREAS, the Parties have determined and hereby represent that they are authorized and empowered to make, execute and deliver this Agreement; that the terms, conditions and provisions of this Agreement are mutually agreeable to the Parties; and that they desire to enter into this Agreement for the purpose of setting forth terms and conditions upon which the City Sewer Line will be constructed and funded.

NOW, THEREFORE, for and in consideration of the mutual promises, covenants, benefits and obligations contained herein, the Parties hereby contract, covenant and agree as follows:

ARTICLE I FUNDING OF CITY SEWER LINE

1.1 Contribution. Developer's estimated proportionate share of the City Sewer Line Costs is provided in **Exhibit "C"** attached hereto. The Parties agree Developer's actual proportionate share of the City Sewer Line Costs will be finalized upon a final accounting of the City Sewer Line Costs following completion and acceptance in accordance with Section 1.3 herein and shall be based on the percentage of the total flow of the basin attributable to the Baker Tract from the City Sewer Line's capacity and planned usage by the development (the "Developer's Share"), as detailed in **Exhibit "C"** attached hereto.

1.2 Developer Incurred Costs. As of the Effective Date of this Agreement, Developer has already incurred certain costs associated with the City Sewer Line, as detailed in **Exhibit "D"** attached hereto (the "Incurred Costs"). The Parties hereby acknowledge that the Incurred Costs are greater than the current estimate of Developer's Share of the City Sewer Line Costs. Accordingly, the Parties hereby agree that Developer shall not be obligated to deposit any funds with the City or otherwise incur any additional costs associated with the City Sewer Line, unless and until it is determined during the closeout process detailed in Section 1.3 that the Developer's Share exceeds the Incurred Costs.

1.3 Closeout. After completion and acceptance of the City Sewer Line, the City will provide an account of the final City Sewer Line Cost and notify the Developer of the final calculation of Developer's Share (the "Accounting Notice"). If Developer's Share exceeds the Incurred Costs, Developer agrees to pay the difference between the Incurred Costs and Developer's Share within thirty (30) days of Developer's receipt of the Accounting Notice. If the Incurred Costs exceed the Developer's Share upon such final accounting, then the City agrees to

refund the difference to Developer within thirty (30) days of the City's delivery of the Accounting Notice to Developer.

ARTICLE II CITY SEWER LINE

2.1 Construction of the City Sewer Line. The Parties acknowledge and agree that the City Sewer Line has been designed and the plans attached hereto as **Exhibit "B"** have been approved by the City. Subject to the conditions of this Agreement, the City shall publicly bid the construction and improvement of the City Sewer Line. The City shall then award the contract(s) to the lowest qualified bidder. After selection of the lowest qualified bidder, the City shall administer the construction contract or contracts for the City Sewer Line in accordance with applicable federal, state, and local laws. A contract for construction of the City Sewer Line shall be approved by the City within six (6) months of the Effective Date of this Agreement and a notice to proceed shall be issued within sixty (60) days of award of the contract. The Parties agree and acknowledge that no such public bid shall proceed until all requisite easements, as provided in Section 2.2 below, have been acquired, delivered, and accepted by the City.

All costs associated with Developer's Share of the City Sewer Line Costs shall be funded in accordance with Article I herein.

2.2 Easement Acquisition. Developer shall obtain all property rights and interests necessary to allow for the construction of the City Sewer Line. Any easements obtained by the Developer for the City Sewer Line shall be assigned to the City and the Developer warrants clear title to such easements from and against all lawful claims and demands of all persons claiming by, through, or under the Developer, subject however to all easements, covenants, conditions, reservations, restrictions and matters of record and any conditions that would be uncovered by an inspection of the easement area or an accurate survey of the same (collectively, the "Permitted Exceptions"), and will defend the City against any adverse claim made against such title, other than the Permitted Exceptions. The Parties hereby agree that all costs associated with such easement acquisition shall be included in the City Sewer Line Costs and Developer shall ultimately only be responsible for funding its proportionate share of such costs in accordance with Article I herein.

Developer shall use commercially reasonable efforts to obtain the easements contemplated by this section. Developer will submit written offer(s) to obtain the easements, based on fair market value of the property interest, to the property owner(s) from whom the property interest is being acquired. If Developer is unable to obtain such easements by private negotiation, the City agrees to consider acquiring such easements required for the City Sewer Line. The Developer must provide the City with a survey and metes and bounds description of the property to be acquired and pay the City for Developer's proportionate share of all costs of obtaining the easements.

Easements required over any portion of the Baker Tract in conjunction with the construction of the City Sewer Line shall be granted by Developer at no cost to the City.

2.3 Reservation of Capacity. The Parties agree the City of Denton retains exclusive ownership of capacity in all the facilities under its ownership and control. The City will reserve capacity in the City Sewer Line to serve the Baker Tract, subject to the terms and conditions of this Agreement.

2.3.1 Upon the City's completion of construction of the City Sewer Line, the City will reserve 224,000 gallons per day of capacity in the City Sewer Line for Developer (the "Reserved Capacity"), as shown on **Exhibit "E"** attached hereto.

2.3.2 Developer acknowledges and agrees the capacity provided by this Agreement runs with the land and shall be an appurtenance to the Baker Tract. Developer acknowledges that recordation of this Agreement in the real property records of Denton County within thirty (30) days of the Effective Date of this Agreement is required; otherwise, the Developer will not be entitled to the Reserved Capacity provided herein and the reservation will expire. Developer shall record this Agreement and provide a recorded copy to the City's Director of Development Services within the earlier of thirty (30) days of the Effective Date of this Agreement or before any transfer of (1) the Baker Tract or (2) any of the Reserved Capacity provided in 2.3.1.

2.3.3 The Reserved Capacity, or any portion thereof, may only be assigned under Section 3.1 as part of a real estate transaction in which the Baker Tract is itself transferred. Developer must provide notice to the City indicating how much of the Reserved Capacity is being assigned ("Capacity Request"). The Capacity Request will be reviewed for written approval by the City, which approval shall not be unreasonably withheld or denied.

2.3.4 DEVELOPER AGREES TO DEFEND, INDEMNIFY, AND HOLD HARMLESS THE CITY OF DENTON FROM ANY AND ALL CLAIMS OF THIRD PARTIES ARISING OUT OF THE DEVELOPER'S TRANSFER OR ASSIGNMENT OF RESERVED CAPACITY UNDER THIS AGREEMENT TO DEVELOPER'S SUBSEQUENT PURCHASERS, SUCCESSORS, AND ASSIGNS.

2.3.5 The reservation of the Reserved Capacity provided by this Agreement shall expire thirty (30) years from the effective date of this Agreement under Section 3.4 herein.

2.3.6 The obligation of the City to provide the Reserved Capacity is conditioned upon present rules, regulations, and statutes of the United States of America and the State of Texas and any court order that directly affects the City of Denton and its provision of wastewater transport and/or treatment services. Developer acknowledges that if the rules, regulations, and statutes of the United States of America and/or the State of Texas that are in effect upon the Effective Date of this Agreement are repealed, revised, or amended to such an extent that the City becomes incapable of, or is legally prevented from, providing the Reserved Capacity, then no liability of any nature is to be imposed upon the City as a result of the City's compliance with such legal or regulatory mandates.

ARTICLE III

MISCELLANEOUS

3.1 Assignability. This Agreement shall not be assigned by the City. Except as provided in Section 2.3, Developer may assign this Agreement, in whole or in part, to a subsequent landowner or developer of the Baker Tract. Developer may only assign this agreement upon written notice thereof to the City and such assignee's agreement to be bound by the terms of this Agreement. The City must provide written approval and consent of any assignment made under this Section.

3.2 Amendments. This Agreement may be changed, amended, or modified only by written instrument with the consent of all Parties.

3.3 Default. In the event the City determines Developer is in violation or default of any of the terms of this Agreement, the City shall provide written notice of such default to Developer with notice of the specific terms and conditions of the violation or default and the requirements to remedy such violation (each, a "Notice of Default").

Upon receipt of a Notice of Default, Developer shall have thirty (30) days from the date of receipt of such Notice of Default to remedy the alleged violation by taking appropriate actions. Such notice or cure period shall not be justification for Developer to cease any of the obligations that might not be the subject of the Notice of Default. In the event Developer fails to cure an alleged violation of this Agreement within the cure period set out above, the violation or default shall be deemed a "Default" hereunder and this Agreement shall terminate and the City will retain any and all remedies available at law or in equity. Notwithstanding the foregoing, if Developer has commenced curing any alleged violation or default within said thirty (30) day period and is diligently prosecuting the same, the City may extend the cure period for an amount of time necessary to cure such violation or default, subject to extension for Force Majeure.

3.4 Termination. This Agreement shall terminate upon the City's completion of the construction of the City Sewer Line or as provided in Sections 2.3, 3.1, 3.3 or 3.16.

3.5 Notice. Any notice, request, demand, instruction or other communication required or permitted to be given to any Party under this Agreement shall be in writing and shall be either (i) personally delivered to the parties named below by a commercial messenger service regularly retaining receipts for such delivery; (ii) sent by registered or certified mail, return receipt requested, effective upon deposit; (iii) delivered by a reputable overnight courier service, effective upon delivery thereof to the carrier; or (iv) sent by electronic mail with confirmation of transmission, and shall be addressed to the parties as listed below:

To the City: City of Denton, Texas
Sara Hensley, City Manager
215 E. McKinney Street
Denton, TX 76201

With Copy to: City of Denton, Texas

Mack Reinwand, City Attorney
215 E. McKinney Street
Denton, TX 76201

To Developer: Denton JV
525 S. Loop 288, Suite 105
Denton, Texas 76205
Attn: Lee Ramsey
Email: lr Ramsey@orisonholdings.com

3.6 Further Acts; Cooperation. Each of the Parties hereto shall execute and deliver all such documents and perform all such acts as reasonably necessary, from time to time, to carry out the matters contemplated by this Agreement.

3.7 No Partnership; Third Parties. It is not intended by this Agreement to, and nothing contained in this Agreement shall, create any owner-contractor, contractor-subcontractor, employer-employee, partnership, joint venture or other arrangement between or among any or all of the Parties hereto. No term or provision of this Agreement is intended to, or shall, be for the benefit of any person, firm, organization or corporation not a Party hereto, and no such other person, firm, organization or corporation shall have any right or cause of action hereunder.

3.8 Remedies. The Parties shall have all rights and remedies at law or in equity under this Agreement for a breach or default under this Agreement.

3.9. Governmental Immunity Not Waived. The City does not waive, nor shall it be deemed hereby to waive, any immunity or defense that would otherwise be available against claims made or arising from any act or omission resulting from this Agreement.

3.10 Entire Agreement. This Agreement contains the entire agreement of the Parties with respect to the subject matter hereof, and this Agreement can be amended only by written agreement signed by all of the Parties hereto. All prior agreements, covenants, representations, or warranties, whether oral or in writing, between the Parties are merged herein.

3.11 Severability. If any provision of this Agreement is declared void or unenforceable, such provision shall be severed from this Agreement.

3.12 Applicable Law and Venue. The construction and validity of this Agreement shall be governed by the laws of the State of Texas and venue for any action brought to enforce this Agreement shall be the state courts of Denton County, Texas.

3.13 Paragraph Headings. The paragraph headings contained in this Agreement are for convenience only and shall in no way enlarge or limit the scope or meaning of the various and several paragraphs hereof.

3.14 Force Majeure. If any Party is unable to perform an obligation under this Agreement (other than monetary obligations) by reason of Force Majeure, then the obligation of such Party, as appropriate, shall be extended or postponed for the period of the actual delay caused by such Force Majeure. The phrase “Force Majeure” shall mean the inability to perform a duty or an obligation due to causes or occurrences which are outside of the control of a Party is postponed and could not be avoided by the exercise of due care on the part of the Party, such as acts of God, pandemics, fires, floods, labor disputes or strikes.

3.15 Counterparts. This Agreement may be executed in two or more counterparts, each of which shall be deemed an original, but all of which together shall constitute one and the same instrument. The signature pages from one or more counterparts may be removed from such counterparts and such signature pages all attached to a single instrument so that the signatures of all Parties may be physically attached to a single document.

3.16 Non-Appropriation. Notwithstanding any provisions contained herein, the obligations of the City under this Agreement are expressly contingent upon the availability of funding for each item and obligation contained herein. The City has appropriated funds for the project in the current fiscal year, however, the Developer shall not have a right of action against the City in the event the City is unable to fulfill its obligations under this Agreement as a result of lack of sufficient funding for any item or obligation from any source utilized to fund this Agreement or failure to budget or authorize funding for this Agreement during the current or future fiscal years. If the City is unable to fulfill its obligations under this Agreement as a result of lack of sufficient funding, or if funds become unavailable, the City, at its sole discretion, may provide funds from a separate source or may terminate this Agreement by written notice at the earliest possible time prior to the end of its fiscal year.

3.17 Effective Date. The Effective Date of this Agreement shall be the date signed by the last Party whose signature makes this Agreement fully executed.

3.18 Form 1295 Certificate of Interested Parties. Prior to execution of this Agreement, Developer agrees to file with the City, pursuant to Texas Government Code Section 2252.908, a signed and completed Texas Ethics Commission (“TEC”) Form 1295 and a certification of filing with the TEC, if required by law.

3.19 Statutory Verifications. The Developer makes the following representations and covenants pursuant to Chapters 2252, 2271, 2274, and 2276, Texas Government Code, as heretofore amended (the “Government Code”), in entering into this Agreement. As used in such verifications, “affiliate” means an entity that controls, is controlled by, or is under common control with Developer within the meaning of SEC Rule 405, 17 C.F.R. § 230.405, and exists to make a profit. Liability for breach of any such verification during the term of this Agreement shall survive until barred by the applicable statute of limitations, and shall not be liquidated or otherwise limited by any provision of this Agreement, notwithstanding anything in this Agreement to the contrary.

Not a Sanctioned Company. The Developer represents that neither it nor any of its parent company, wholly- or majority-owned subsidiaries, and other affiliates is a company identified on a list prepared and maintained by the Texas Comptroller of Public Accounts under Section 2252.153 or Section 2270.0201, Government Code. The foregoing representation excludes Developer and each of its parent company, wholly- or majority-owned subsidiaries, and other affiliates, if any, that the United States government has affirmatively declared to be excluded from its federal sanctions regime relating to Sudan or Iran or any federal sanctions regime relating to a foreign terrorist organization.

No Boycott of Israel. The Developer hereby verifies that it and its parent company, wholly- or majority-owned subsidiaries, and other affiliates, if any, do not boycott Israel and will not boycott Israel during the term of this Agreement. As used in the foregoing verification, “boycott Israel” has the meaning provided in Section 2271.001, Government Code.

No Discrimination Against Firearm Entities. The Developer hereby verifies that it and its parent company, wholly- or majority-owned subsidiaries, and other affiliates, if any, do not have a practice, policy, guidance, or directive that discriminates against a firearm entity or firearm trade association and will not discriminate against a firearm entity or firearm trade association during the term of this Agreement. As used in the foregoing verification, “discriminate against a firearm entity or firearm trade association” has the meaning provided in Section 2274.001(3), Government Code.

No Boycott of Energy Companies. The Developer hereby verifies that it and its parent company, wholly- or majority-owned subsidiaries, and other affiliates, if any, do not boycott energy companies and will not boycott energy companies during the term of this Agreement. As used in the foregoing verification, “boycott energy companies” has the meaning provided in Section 2276.001(1), Government Code.

[THE REMAINDER OF THIS PAGE INTENTIONALLY LEFT BLANK]

Executed by the City and Developer to be effective on the Effective Date.

CITY OF DENTON, TEXAS

By: _____
Name: _____
Title: _____
Date: _____

ATTEST:


By: _____
Name: _____
Title: _____

DEVELOPER:

DENTON JV

By: RM Squared Denton, LLC,
a Texas limited liability company

By: BLTJ Management, LLC,
a Texas limited liability company
its Manager

By: 
Name: Brandon Martino
Title: President

By: Baker 345, LLC
a Texas limited liability company



By: 
Name: Robert J. Widmer, Jr.
Title: Secretary

EXHIBIT “A”
Developer Property Description

EXHIBIT A



21.49 ACRES

331.22 ACRES

Baker Tract
Denton, Texas
October 2025

Kimley»Horn
6160 Warren Parkway, Suite 210
Frisco, Texas 75034
972-335-3580
State of Texas Registration No. F-928

EXHIBIT “B”
City Sewer Line


Plotted By: Browning, Mason Sheet Set: Warrant #XXXX Layout: Layout1 June 11, 2025 09:35:29am K:\Yr Civil\063248015 - baker tract offsite sewer\CAD\plansheets\C-Cover.dwg
This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.

CIVIL CONSTRUCTION PLANS FOR BAKER TRACT OFFSITE SEWER

JIM CRISTAL ROAD TO HAMPTON ROAD
CITY OF DENTON
DENTON COUNTY, TEXAS

PLANS SUBMITTAL/REVIEW LOG

40% SUBMITTAL - NOT FOR CONSTRUCTION.	02/03/2025
60% SUBMITTAL - NOT FOR CONSTRUCTION.	03/26/2025
90% SUBMITTAL - NOT FOR CONSTRUCTION.	04/21/2025
100% SUBMITTAL	06/11/2025



SITE LOCATION MAP
(NOT TO SCALE)

- NOTES:
1. THE SITEWORK FOR THE PROJECT SHALL MEET OR EXCEED THE STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION FOR THE NCTCOG - NORTH CENTRAL TEXAS COUNCIL OF GOVERNMENTS (LATEST EDITION), THE CITY STANDARDS, AND ANY SPECIAL PROVISIONS ADOPTED BY THE CITY. CITY STANDARDS GOVERN OVER NCTCOG IN THE EVENT OF A CONFLICT.
 2. ALL NECESSARY INSPECTIONS AND/OR CERTIFICATIONS REQUIRED BY CODES AND/OR UTILITY SERVICE COMPANIES SHALL BE PERFORMED PRIOR TO CONTRACT COMPLETION AND THE FINAL CONNECTION OF SERVICES.
 3. IF REPRODUCED, THE SCALES SHOWN ON THESE PLANS ARE BASED ON A 24" X 36" SHEET.



INDEX OF SHEETS

SHEET NO.	DESCRIPTION	DATE	REVISION
C1.01	COVER SHEET	06/11/2025	
C2.01	GENERAL NOTES	06/11/2025	
C2.02	COD GENERAL NOTES	06/11/2025	
C13.01	SEWER INDEX SHEET	06/11/2025	
C13.02	SEWER PLAN AND PROFILE	06/11/2025	
C13.03	SEWER PLAN AND PROFILE	06/11/2025	
C13.04	SEWER PLAN AND PROFILE	06/11/2025	
C13.05	SEWER PLAN AND PROFILE	06/11/2025	
C13.06	SEWER PLAN AND PROFILE	06/11/2025	
C13.07	SEWER PLAN AND PROFILE	06/11/2025	
C13.08	SEWER PLAN AND PROFILE	06/11/2025	
C13.09	SEWER PLAN AND PROFILE	06/11/2025	
C13.10	SEWER PLAN AND PROFILE	06/11/2025	
C13.11	SEWER PLAN AND PROFILE	06/11/2025	
C13.12	SEWER PLAN AND PROFILE	06/11/2025	
C13.13	LIFT STATION ABANDONMENT & SALVAGE PLAN	06/11/2025	
C13.14	LIFT STATION ABANDONMENT & SALVAGE PLAN	06/11/2025	
C17.01	EROSION CONTROL PLAN	06/11/2025	
C17.02	EROSION CONTROL PLAN	06/11/2025	
C17.03	EROSION CONTROL PLAN	06/11/2025	
C17.04	EROSION CONTROL PLAN	06/11/2025	
C17.05	EROSION CONTROL PLAN	06/11/2025	
C17.06	EROSION CONTROL PLAN	06/11/2025	
C17.07	EROSION CONTROL PLAN	06/11/2025	
C17.08	EROSION CONTROL PLAN	06/11/2025	
C17.09	EROSION CONTROL PLAN	06/11/2025	
C17.10	EROSION CONTROL PLAN	06/11/2025	
C17.11	EROSION CONTROL PLAN	06/11/2025	
C17.12	EROSION CONTROL DETAILS	06/11/2025	
C18.01	CONSTRUCTION DETAILS	06/11/2025	
C18.02	CONSTRUCTION DETAILS	06/11/2025	
C18.03	CONSTRUCTION DETAILS	06/11/2025	
C18.04	CONSTRUCTION DETAILS	06/11/2025	
C18.05	CONSTRUCTION DETAILS	06/11/2025	

ENGINEER



Kimley»Horn


6160 WARREN PARKWAY
SUITE 210
FRISCO, TEXAS 75034
PH. (972) 335-3580
CONTACT: JOHN HALE, P.E.




STATE OF TEXAS
REGISTRATION NO. F-928

JUNE 2025





SCALE	AS SHOWN		Kimley»Horn 3525 KIMLEY-HORN ASSOCIATES, INC. 6180 WARREN PARKWAY, SUITE 200, FRESCO, TX 75034 PHONE: 972-355-3580 WWW.KIMLEY-HORN.COM TEXAS REGISTERED ENGINEERING FIRM E-928	No. _____ REVISIONS _____ DATE _____
DESIGNED BY	JOHN			
DRAWN BY	JNC			
CHECKED BY	JTH			
BAKER TRACT OFFSITE SEWER CITY OF DENTON, TEXAS			SEWER INDEX SHEET	
DATE 06/11/25			PROJECT NO. 063248015	
SHEET NUMBER C13.01				



1. REFER TO DETAILS FOR SANITARY SEWER MANHOLE REQUIREMENTS.
2. REFER TO DETAILS FOR TRENCHING, BEDDING, BACK FILL, AND TRENCH COMPACTION REQUIREMENTS.
3. MANHOLES 20" OR GREATER IN DEPTH SHALL BE MONOLITHICALLY PRECAST FIBERGLASS.
4. CONTRACTOR SHALL INSTALL VENT 1' ABOVE 100-YEAR FLOOD ELEVATION PER CITY OF DENTON DETAILS.
5. CONTRACTOR SHALL MATCH MANHOLE LID TO FINISHED GRADE.

BENCHMARKS


BM #51 - (X) SET, on concrete curb located ±47 feet northwest from intersection of N. Masch Branch Road and Hampton Road.
Elevation: 676.78'

Site Benchmark - (X) SET, on concrete curb located ±950 feet north of W. University Drive (US Hwy 380) and ±984 feet west of N. Masch Branch Road in entrance of Fisher 59 Food Supply.
Elevation: 669.09'

Site Benchmark - (X) SET, on southeast corner of concrete curb inlet located ±850 feet west of intersection at N. Masch Branch Road and W. University Drive (U.S. Hwy 380).
Elevation: 6658.86'




Know what's **below**.
Call before you dig.


C13.02		SHEET NUMBER	PROJECT NO. 063248015	DATE 06/11/25	<p>BAKER TRACT OFFSITE SEWER CITY OF DENTON, TEXAS</p>		<p>SEWER PLAN AND PROFILE</p>		<p>SCALE AS SHOWN DESIGNED BY JNC. DRAWN BY JNC. CHECKED BY JTH</p>		<p>Kimley»Horn © 2025 KIMLEY-HORN AND ASSOCIATES, INC. 6160 WARREN PARKWAY, SUITE 210, FRISCO, TX 75034 PHONE: 972-335-9980 WWW.KIMLEY-HORN.COM TEXAS REGISTERED ENGINEERING FIRM F-928</p>	<p>No.</p> <p>REVISIONS</p> <p>DATE</p>
--------	--	--------------	--------------------------	------------------	---	--	--	--	---	---	--	---

Plotted By: Browning, Mason Date: June 11, 2025 08:35:16am File Path: K:\Yr1_civil\063248015 - baker tract offsite sewer\CAD\plansheets\C-SWR - P&P.dwg


This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



SEWER LINE A



PROFILE SCALE
1" = 40' HORIZONTAL
1" = 4' VERTICAL



LEGEND

---	PROPERTY LINE
---	PROPOSED EASEMENT
SS	PROPOSED SANITARY SEWER LINE
OP	EXISTING OVERHEAD POWER LINE
CL	EXISTING CABLE LINE
GL	EXISTING GAS LINE
WL	EXISTING WATER LINE
SS	EXISTING SANITARY SEWER LINE
---	EXISTING FLOODPLAIN
---	ABANDON IN PLACE
SS	PROPOSED SANITARY SEWER MANHOLE (SS MH)
●	PROPOSED DOUBLE CLEAN-OUT
●	PROPOSED CLEAN-OUT
○	EXISTING POWER POLE
○	EXISTING FIRE HYDRANT
○	EXISTING STORM MANHOLE
○	EXISTING SAN. SWR. MANHOLE
○	EXISTING SIGN
---	REMOVE AND REPLACE GRAVEL DRIVE
---	PAVEMENT IMPROVEMENTS PER MASCH BRANCH ROAD PLANS BY KIMLEY-HORN

UTILITY NOTES

1. REFER TO DETAILS FOR SANITARY SEWER MANHOLE REQUIREMENTS.
2. REFER TO DETAILS FOR TRENCHING, BEDDING, BACK FILL, AND TRENCH COMPACTION REQUIREMENTS.
3. MANHOLES 20' OR GREATER IN DEPTH SHALL BE MONOLITHICALLY PRECAST FIBERGLASS.
4. CONTRACTOR SHALL INSTALL VENT 1' ABOVE 100-YEAR FLOOD ELEVATION PER CITY OF DENTON DETAILS.
5. CONTRACTOR SHALL MATCH MANHOLE LID TO FINISHED GRADE.

BENCHMARKS





BM #61 - "X" SET, on concrete curb located ±47 feet northwest from intersection of N. Masch Branch Road and Hampton Road.
Elevation: 676.76'


Site Benchmark - "X" SET, on concrete curb located ±950 feet north of W. University Drive (US Hwy 380) and ± 984 feet west of N. Masch Branch Road in entrance of Fisher 59 Food Supply.
Elevation: 669.09'

Site Benchmark - "X" SET, on southeast corner of concrete curb inlet located ± 850 feet west of intersection at N. Masch Branch Road and W. University Drive (U.S. Hwy 380).
Elevation: 6658.86'





				DATE	
				REVISIONS	
				No.	
Kimley»Horn © 2025 KIMLEY-HORN AND ASSOCIATES, INC. 6160 WARREN PARKWAY, SUITE 210, FRISCO, TX 75034 PHONE: 972-335-3580 WWW.KIMLEY-HORN.COM TEXAS REGISTERED ENGINEERING FIRM F-928					
SCALE	AS SHOWN	DESIGNED BY	DRAWN BY	CHECKED BY	JTH
SEWER PLAN AND PROFILE					
BAKER TRACT OFFSITE SEWER CITY OF DENTON, TEXAS					
DATE 06/11/25					
PROJECT NO. 063248015					
SHEET NUMBER C13.03					



<p>BAKER TRACT OFFSITE SEWER CITY OF DENTON, TEXAS</p>		<p>SEWER PLAN AND PROFILE</p>		<p>SCALE AS SHOWN DESIGNED BY JOHN DRAWN BY INC. CHECKED BY JTH</p>				<p>Kimley»Horn © 2025 KIMLEY-HORN AND ASSOCIATES, INC. 6160 WARREN PARKWAY, SUITE 210, FRISCO, TX 75034 PHONE: 972-355-3580 WWW.KIMLEY-HORN.COM TEXAS REGISTERED ENGINEERING FIRM F-928</p>		<p>No. _____</p> <p>REVISIONS _____</p> <p>DATE _____</p>	
<p>DATE 06/11/25</p>		<p>PROJECT NO. 063248015</p>		<p>SHEET NUMBER C13.04</p>							

Plotted By: Browning, Mason Date: June 11, 2025 08:36:13am File Path: K:\Yr1_civil\063248015 - baker tract offsite sewer\CAD\plansheets\C-SWR - P&P.dwg

This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.




LEGEND

- PROPERTY LINE
- PROPOSED EASEMENT
- PROPOSED SANITARY SEWER LINE
- EXISTING OVERHEAD POWER LINE
- EXISTING CABLE LINE
- EXISTING GAS LINE
- EXISTING WATER LINE
- EXISTING SANITARY SEWER LINE
- EXISTING FLOODPLAIN
- ABANDON IN PLACE
- PROPOSED SANITARY SEWER MANHOLE (SS MH)
- PROPOSED DOUBLE CLEAN-OUT
- PROPOSED CLEAN-OUT
- EXISTING POWER POLE
- EXISTING FIRE HYDRANT
- EXISTING STORM MANHOLE
- EXISTING SAN. SWR. MANHOLE
- EXISTING SIGN
- REMOVE AND REPLACE GRAVEL DRIVE
- PAVEMENT IMPROVEMENTS PER MASCH BRANCH ROAD PLANS BY KIMLEY-HORN

UTILITY NOTES

- REFER TO DETAILS FOR SANITARY SEWER MANHOLE REQUIREMENTS.
- REFER TO DETAILS FOR TRENCHING, BEDDING, BACK FILL, AND TRENCH COMPACTION REQUIREMENTS.
- MANHOLES 20' OR GREATER IN DEPTH SHALL BE MONOLITHICALLY PRECAST FIBERGLASS.
- CONTRACTOR SHALL INSTALL VENT 1' ABOVE 100-YEAR FLOOD ELEVATION PER CITY OF DENTON DETAILS.
- CONTRACTOR SHALL MATCH MANHOLE LID TO FINISHED GRADE.



BENCHMARKS

BM #61 - "X" SET, on concrete curb located ±47 feet northwest from intersection of N. Masch Branch Road and Hampton Road. Elevation: 676.76'

Site Benchmark - "X" SET, on concrete curb located ±950 feet north of W. University Drive (US Hwy 380) and ± 984 feet west of N. Masch Branch Road in entrance of Fisher 59 Food Supply. Elevation: 669.09'



Site Benchmark - "X" SET, on southeast corner of concrete curb inlet located ± 850 feet west of intersection at N. Masch Branch Road and W. University Drive (U.S. Hwy 380). Elevation: 6658.86'



Kimley»Horn			
© 2025 KIMLEY-HORN AND ASSOCIATES, INC. 6180 WARREN PARKWAY, SUITE 210, FRISCO, TX 75034 PHONE: 972-355-3580 WWW.KIMLEY-HORN.COM TEXAS REGISTERED ENGINEERING FIRM F-928			
STATE OF TEXAS JOHN HALE 145933 LICENSED PROFESSIONAL ENGINEER 06/17/2025			
SCALE AS SHOWN	DESIGNED BY JNC	DRAWN BY JNC	CHECKED BY JTH
SEWER PLAN AND PROFILE			
BAKER TRACT OFFSITE SEWER CITY OF DENTON, TEXAS			
DATE 06/11/25			
PROJECT NO. 063248015			
SHEET NUMBER C13.05			
REVISIONS			DATE
No.			

Plotted By: Browning, Mason Date: June 11, 2025 08:36:45pm File Path: K:\Vri_civil\063248015 - baker tract offsite sewer\CAD plansheets\C-SWR - P&P.dwg

This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.




LEGEND

- PROPERTY LINE
- PROPOSED EASEMENT
- SS PROPOSED SANITARY SEWER LINE
- CHP PROPOSED OVERHEAD POWER LINE
- CBL EXISTING CABLE LINE
- GAS EXISTING GAS LINE
- W EXISTING WATER LINE
- SS EXISTING SANITARY SEWER LINE
- EXISTING FLOODPLAIN
- ABANDON IN PLACE
- PROPOSED SANITARY SEWER MANHOLE (SS MH)
- PROPOSED DOUBLE CLEAN-OUT
- PROPOSED CLEAN-OUT
- EXISTING POWER POLE
- EXISTING FIRE HYDRANT
- EXISTING STORM MANHOLE
- EXISTING SAN. SWR. MANHOLE
- EXISTING SIGN
- REMOVE AND REPLACE GRAVEL DRIVE
- PAVEMENT IMPROVEMENTS PER MASCH BRANCH ROAD PLANS BY KIMLEY-HORN

- UTILITY NOTES**
- REFER TO DETAILS FOR SANITARY SEWER MANHOLE REQUIREMENTS.
 - REFER TO DETAILS FOR TRENCHING, BEDDING, BACK FILL, AND TRENCH COMPACTION REQUIREMENTS.
 - MANHOLES 20' OR GREATER IN DEPTH SHALL BE MONOLITHICALLY PRECAST FIBERGLASS.
 - CONTRACTOR SHALL INSTALL VENT 1' ABOVE 100-YEAR FLOOD ELEVATION PER CITY OF DENTON DETAILS.
 - CONTRACTOR SHALL MATCH MANHOLE LID TO FINISHED GRADE.

PROFILE SCALE
1" = 40' HORIZONTAL
1" = 4' VERTICAL



BENCHMARKS

BM #61 - "X" SET, on concrete curb located ±47 feet northwest from intersection of N. Masch Branch Road and Hampton Road. Elevation: 676.76'

Site Benchmark - "X" SET, on concrete curb located ±950 feet north of W. University Drive (US Hwy 380) and ± 984 feet west of N. Masch Branch Road in entrance of Fisher 59 Food Supply. Elevation: 669.09'




Site Benchmark - "X" SET, on southeast corner of concrete curb inlet located ± 850 feet west of intersection at N. Masch Branch Road and W. University Drive (U.S. Hwy 380). Elevation: 6658.86'























DESIGNED BY JNC		DRAWN BY JNC		CHECKED BY JTH	
SEWER PLAN AND PROFILE					
BAKER TRACT OFFSITE SEWER CITY OF DENTON, TEXAS					
DATE 06/11/25					
PROJECT NO. 063248015					
SHEET NUMBER C13.06					
REVISIONS				DATE	
No.					

Kimley»Horn
© 2025 KIMLEY-HORN AND ASSOCIATES, INC.
6160 WARREN PARKWAY, SUITE 210, FRISCO, TX 75034
PHONE: 972-355-3580
WWW.KIMLEY-HORN.COM
TEXAS REGISTERED ENGINEERING FIRM F-928

STATE OF TEXAS
JOHN HALE
145933
LICENSED PROFESSIONAL ENGINEER
06/17/2025



LEGEND

- | | |
|---|---|
|  | PROPERTY LINE |
|  | PROPOSED EASEMENT |
|  | PROPOSED SANITARY SEWER LINE |
|  | EXISTING OVERHEAD POWER LINE |
|  | EXISTING CABLE LINE |
|  | EXISTING GAS LINE |
|  | EXISTING WATER LINE |
|  | EXISTING SANITARY SEWER LINE |
|  | EXISTING FLOODPLAIN |
|  | ABANDON IN PLACE |
|  | PROPOSED SANITARY SEWER MANHOLE (SS MH) |
|  | PROPOSED DOUBLE CLEAN-OUT |
|  | PROPOSED CLEAN-OUT |
|  | EXISTING POWER POLE |
|  | EXISTING FIRE HYDRANT |
|  | EXISTING STORM MANHOLE |
|  | EXISTING SAN. SWR. MANHOLE |
|  | EXISTING SIGN |
|  | REMOVE AND REPLACE GRAVEL DRIVE |
|  | PAVEMENT IMPROVEMENTS PER MASCH
BRANCH ROAD PLANS BY KIMLEY-HORN |

UTILITY NOTES

1. REFER TO DETAILS FOR SANITARY SEWER MANHOLE REQUIREMENTS.
2. REFER TO DETAILS FOR TRENCHING, BEDDING, BACK FILL, AND TRENCH COMPACTION REQUIREMENTS.
3. MANHOLES 20" OR GREATER IN DEPTH SHALL BE MONOLITHICALLY PRECAST FIBERGLASS.
4. CONTRACTOR SHALL INSTALL VENT 1' ABOVE 100-YEAR FLOOD ELEVATION PER CITY OF DENTON DETAILS.
5. CONTRACTOR SHALL MATCH MANHOLE LID TO FINISHED GRADE.

BENCHMARKS


BM #51 - (X) SET, on concrete curb located ±47 feet northwest from intersection of N. Masch Branch Road and Hampton Road.
Elevation: 676.78'

Site Benchmark - (X) SET, on concrete curb located ±950 feet north of W. University Drive (US Hwy 380) and ±984 feet west of N. Masch Branch Road in entrance of Fisher 59 Food Supply.
Elevation: 669.09'

Site Benchmark - (X) SET, on southeast corner of concrete curb inlet located ±850 feet west of intersection at N. Masch Branch Road and W. University Drive (U.S. Hwy 380).
Elevation: 6658.86'




Know what's **below**.
Call before you dig.


<p>BAKER TRACT OFFSITE SEWER CITY OF DENTON, TEXAS</p>		<p>SEWER PLAN AND PROFILE</p>		<p>SCALE AS SHOWN DESIGNED BY JNC. DRAWN BY JNC. CHECKED BY JTH</p>				<p>Kimley»Horn © 2025 KIMLEY-HORN AND ASSOCIATES, INC. 6160 WARREN PARKWAY, SUITE 210, FRISCO, TX 75034 PHONE: 972-335-9980 WWW.KIMLEY-HORN.COM TEXAS REGISTERED ENGINEERING FIRM F-928</p>		<p>No.</p> <p>REVISIONS</p> <p>DATE</p>	
<p>C13.08</p>		<p>SHEET NUMBER</p>		<p>PROJECT NO. 063248015</p>		<p>DATE 06/11/25</p>					

Plotted By: Browning, Mason Date: June 11, 2025 08:38:09am File Path: K:\Vri_civil\063248015 - baker tract offsite sewer\CAD plansheets\C-SWR - P&P.dwg


This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



SEWER LINE A



PROFILE SCALE
1" = 40' HORIZONTAL
1" = 4' VERTICAL



LEGEND

- PROPERTY LINE
- PROPOSED EASEMENT
- PROPOSED SANITARY SEWER LINE
- EXISTING OVERHEAD POWER LINE
- EXISTING CABLE LINE
- EXISTING GAS LINE
- EXISTING WATER LINE
- EXISTING SANITARY SEWER LINE
- EXISTING FLOODPLAIN
- ABANDON IN PLACE
- PROPOSED SANITARY SEWER MANHOLE (SS MH)
- PROPOSED DOUBLE CLEAN-OUT
- PROPOSED CLEAN-OUT
- EXISTING POWER POLE
- EXISTING FIRE HYDRANT
- EXISTING STORM MANHOLE
- EXISTING SAN. SWR. MANHOLE
- EXISTING SIGN
- REMOVE AND REPLACE GRAVEL DRIVE
- PAVEMENT IMPROVEMENTS PER MASCH BRANCH ROAD PLANS BY KIMLEY-HORN

UTILITY NOTES

- REFER TO DETAILS FOR SANITARY SEWER MANHOLE REQUIREMENTS.
- REFER TO DETAILS FOR TRENCHING, BEDDING, BACK FILL, AND TRENCH COMPACTION REQUIREMENTS.
- MANHOLES 20' OR GREATER IN DEPTH SHALL BE MONOLITHICALLY PRECAST FIBERGLASS.
- CONTRACTOR SHALL INSTALL VENT 1' ABOVE 100-YEAR FLOOD ELEVATION PER CITY OF DENTON DETAILS.
- CONTRACTOR SHALL MATCH MANHOLE LID TO FINISHED GRADE.

BENCHMARKS

BM #61 - "X" SET, on concrete curb located ±47 feet northwest from intersection of N. Masch Branch Road and Hampton Road.
Elevation: 676.76'

Site Benchmark - "X" SET, on concrete curb located ±950 feet north of W. University Drive (US Hwy 380) and ± 984 feet west of N. Masch Branch Road in entrance of Fisher 59 Food Supply.
Elevation: 669.09'

Site Benchmark - "X" SET, on southeast corner of concrete curb inlet located ± 850 feet west of intersection at N. Masch Branch Road and W. University Drive (U.S. Hwy 380).
Elevation: 6658.86'








No.		REVISIONS	DATE
No.		REVISIONS	DATE


Kimley»Horn
© 2025 KIMLEY-HORN AND ASSOCIATES, INC.
6160 WARREN PARKWAY, SUITE 210, FRISCO, TX 75034
PHONE: 972-335-3580
WWW.KIMLEY-HORN.COM
TEXAS REGISTERED ENGINEERING FIRM F-928


SEWER PLAN AND PROFILE

**BAKER TRACT
OFFSITE SEWER
CITY OF DENTON, TEXAS**

DATE: 06/11/25
PROJECT NO.: 063248015
SHEET NUMBER: C13.09



C13.10	SHEET NUMBER	PROJECT NO. 063248015	DATE 06/11/25	BAKER TRACT OFFSITE SEWER CITY OF DENTON, TEXAS	SEWER PLAN AND PROFILE	SCALE	DESIGNED BY JNC	DRAWN BY JNC	CHECKED BY JTH		Kimley»»Horn © 2025 KIMLEY-HORN AND ASSOCIATES, INC. 6100 WARREN • DALLAS, TX 75204 PHONE: 972-335-3580 WWW.KIMLEY-HORN.COM TEXAS REGISTERED ENGINEERING FIRM F-628	No.	REVISIONS	DATE



1. REFER TO DETAILS FOR SANITARY SEWER MANHOLE REQUIREMENTS.
2. REFER TO DETAILS FOR TRENCHING, BEDDING, BACK FILL, AND TRENCH COMPACTION REQUIREMENTS.
3. MANHOLES 20' OR GREATER IN DEPTH SHALL BE MONOLITHICALLY PRECAST FIBERGLASS.
4. CONTRACTOR SHALL INSTALL VENT 1' ABOVE 100-YEAR FLOOD ELEVATION PER CITY OF DENTON DETAILS.
5. CONTRACTOR SHALL MATCH MANHOLE LID TO FINISHED GRADE.




BM #61 - "X" SET, on concrete curb located ±47 feet northwest from intersection of N. Masch Branch Road and Hampton Road.
Elevation: 676.76'

Site Benchmark - "X" SET, on concrete curb located ±950 feet north of W. University Drive (US Hwy 380) and ± 984 feet west of N. Masch Branch Road in entrance of Fisher 59 Food Supply.
Elevation: 669.09'

Site Benchmark - "X" SET, on southeast corner of concrete curb inlet located ± 850 feet west of intersection at N. Masch Branch Road and W. University Drive (US Hwy 380).
Elevation: 665.86'



Kimley»»Horn
© 2025 KIMLEY-HORN AND ASSOCIATES, INC.
6160 WARREN PARKWAY, SUITE 210, FRISCO, TX 75034
PHONE: 972-335-3580
WWW.KIMLEY-HORN.COM
TEXAS REGISTERED ENGINEERING FIRM F-928



SCALE	AS SHOWN	DESIGNED BY	JNC	DRAWN BY	JNC	CHECKED BY	JTH
-------	----------	-------------	-----	----------	-----	------------	-----

SEWER PLAN AND PROFILE


**BAKER TRACT
OFFSITE SEWER
CITY OF DENTON, TEXAS**

DATE
06/11/25

PROJECT NO
063248015


SHEET NUMB

C13.1



Plotted By: Browning, Moson Date: June 11, 2025 08:40:06am File Path: \\k:_civil\063248015 - baker tract offsite sewer\CAD\plansheets\C-Demo.dwg

This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



NORTH


GRAPHIC SCALE IN FEET

LEGEND

- Grout fill and abandon
- Abandon in place
- Remove (same trench)

NOTES:

- ALL HARDWARE ITEMS ARE TO BE SALVAGED AND DELIVERED TO THE PUBLIC WORKS BUILDING INCLUDING THE CONTROL PANEL.
- ALL ITEMS REMOVED THAT ARE NOT DELIVERED TO THE PUBLIC WORKS BUILDING SHALL BE PROPERLY DISPOSED OF OFF-SITE.
- THE DIRECTOR OF PUBLIC WORKS SHALL BE CONSULTED ON WHAT SHALL BE DELIVERED TO THE PUBLIC WORKS BUILDING.
- ALL PIPING INDICATED TO BE REMOVED SHALL BE PROPERLY DISPOSED OF OFF-SITE.
- MASCH BRANCH LIFT STATION TAKEN FROM MARRIOTT GARDENS ADDITION PLANS DATED 2/24/1997 BY HAMMETT & NASH, INC.
- CONTRACTOR SHALL VERIFY HORIZONTAL AND VERTICAL LOCATION OF EXISTING WET WELL, APPURTENANCES, AND FORCE MAIN PRIOR TO CONSTRUCTION.



BENCHMARKS

BM #61 - "X" SET, on concrete curb located ±47 feet northwest from intersection of N. Masch Branch Road and Hampton Road.
Elevation: 676.76'

Site Benchmark - "X" SET, on concrete curb located ±950 feet north of W. University Drive (US Hwy 380) and ± 984 feet west of N. Masch Branch Road in entrance of Fisher 59 Food Supply.
Elevation: 669.09'

Site Benchmark - "X" SET, on southeast corner of concrete curb inlet located ± 850 feet west of intersection at N. Masch Branch Road and W. University Drive (U.S. Hwy 380).
Elevation: 6658.86'

CAUTION!!

THE CONTRACTOR SHALL FIELD VERIFY THE HORIZONTAL AND VERTICAL LOCATIONS OF ALL EXISTING UTILITIES PRIOR TO START OF CONSTRUCTION AND SHALL NOTIFY THE CONSTRUCTION MANAGER AND ENGINEER OF ANY CONFLICTS DISCOVERED. CONTRACTOR IS RESPONSIBLE FOR PROTECTING EXISTING UTILITIES (SHOWN OR NOT SHOWN) WITHIN SCOPE OF CONSTRUCTION. IF ANY EXISTING UTILITIES ARE DAMAGED, THE CONTRACTOR SHALL REPLACE THEM AT HIS OWN EXPENSE. CALL 811 AT LEAST 72 HOURS PRIOR TO COMMENCING CONSTRUCTION IN VICINITY.

Know what's below.
Call before you dig.

SCALE	DESIGNED BY	DRAWN BY	CHECKED BY	REVISIONS	DATE
AS SHOWN	JNC	JNC	JTH		


Kimley»Horn

© 2025 KIMLEY-HORN AND ASSOCIATES, INC.
6180 WARREN PARKWAY, SUITE 210, FRISCO, TX 75034
PHONE: 972-335-3580
WWW.KIMLEY-HORN.COM
TEXAS REGISTERED ENGINEERING FIRM F-928

LIFT STATION
ABANDONMENT &
SALVAGE PLAN


BAKER TRACT
OFFSITE SEWER
CITY OF DENTON, TEXAS

DATE	06/11/25
PROJECT NO.	063248015
SHEET NUMBER	C13.13



SECTION A

SCALE: 1/8" = 1"



VOID BACKFILL DETAIL

SCALE: NOT TO SCALE

- NOTES:**
1. ALL HARDWARE ITEMS ARE TO BE SALVAGED AND DELIVERED TO THE PUBLIC WORKS BUILDING INCLUDING THE CONTROL PANEL.
 2. ALL ITEMS REMOVED THAT ARE NOT DELIVERED TO THE PUBLIC WORKS BUILDING SHALL BE PROPERLY DISPOSED OF OFF-SITE.
 3. THE DIRECTOR OF PUBLIC WORKS SHALL BE CONSULTED ON WHAT SHALL BE DELIVERED TO THE PUBLIC WORKS BUILDING.
 4. ALL PIPING INDICATED TO BE REMOVED SHALL BE PROPERLY DISPOSED OF OFF-SITE.

BENCHMARKS

BM #61 - "X" SET, on concrete curb located +47 feet northwest from intersection of N. Masch Branch Road and Hampton Road.
Elevation: 676.76'


Site Benchmark - "X" SET, on concrete curb located ±950 feet north of W. University Drive (US Hwy 380) and ± 984 feet west of N. Masch Branch Road in entrance of Fisher 59 Food Supply.
Elevation: 669.09'



Site Benchmark - "X" SET, on southeast corner of concrete curb located ± 850 feet west of intersection at N. Masch Branch Road and W. University Drive (U.S. Hwy 380).
Elevation: 6658.86'

THE CONTRACTOR SHALL FIELD VERIFY THE HORIZONTAL AND VERTICAL LOCATIONS OF ALL EXISTING UTILITIES PRIOR TO START OF CONSTRUCTION AND SHALL NOTIFY THE CONSTRUCTION MANAGER OF ANY CONFLICTS DISCOVERED. CONTRACTOR IS RESPONSIBLE FOR PROTECTING EXISTING UTILITIES (SHOWN OR NOT SHOWN) WITHIN SCOPE OF CONSTRUCTION. IF ANY EXISTING UTILITIES ARE DAMAGED, THE CONTRACTOR SHALL REPLACE THEM AT HIS OWN EXPENSE. CALL 811 AT LEAST 72 HOURS PRIOR TO COMMENCING CONSTRUCTION IN VICINITY.




Know what's **below**.
Call before you dig.

<p>BAKER TRACT OFFSITE SEWER CITY OF DENTON, TEXAS</p>		<p>LIFT STATION ABANDONMENT & SALVAGE PLAN</p>		<p>SCALE AS SHOWN DESIGNED BY JNC DRAWN BY JNC CHECKED BY JTH</p>		<p>Kimley»Horn © 2025 KIMLEY-HORN AND ASSOCIATES, INC. 6160 WARREN PARKWAY, SUITE 210, FRISCO, TX 75034 PHONE: 972-335-3580 WWW.KIMLEY-HORN.COM TEXAS REGISTERED ENGINEERING FIRM F-928</p>	<p>No.</p> <p>REVISIONS</p> <p>DATE</p>
<p>SHEET NUMBER</p>		<p>PROJECT NO.</p>		<p>DATE</p>		<p>06/11/25</p>	
<p>C13.14</p>		<p>063248015</p>		<p>06/11/25</p>			



GRAPHIC SCALE IN FEET

LEGEND



EROSION CONTROL SCHEDULE AND PHASING

THE PROJECT SHALL GENERALLY CONFORM TO THE FOLLOWING

- PHASE A - GRADING
1. CONSTRUCT TEMPORARY CONSTRUCTION ENTRANCE, SILT FENCE, DIKE, AND TREE PROTECTION FENCE ACCORDING TO THE APPROXIMATE LOCATION AND SHOWN ON EROSION CONTROL PLAN NOTES AND DETAIL SHEET.
 2. BEGIN CLEARING AND GRADING OF SITE.
 3. SEED AND REVEGETATE SLOPES WHERE SHOWN.
- PHASE B - UTILITIES
1. KEEP ALL STORM WATER POLLUTION PREVENTION MEASURES IN PLACE.
 2. INSTALL STORM DRAINS, SANITARY SEWER, AND WATER AS SPECIFIED ON PLAN SHEETS.
- PHASE C - LANDSCAPING AND SOIL STABILIZATION.
1. REVEGETATE LOT AND PARKWAYS
 2. LANDSCAPE CONTRACTOR SHALL REVEGETATE ALL AREAS RESERVED FOR LANDSCAPE VEGETATIVE COVERS.
 3. REMOVE EROSION CONTROL DEVICES WHEN MINIMUM 70% GROUND COVER IS ESTABLISHED.
- EROSION CONTROL MEASUREMENT MUST BE ESTABLISHED BEFORE STRUCTURAL CONTROLS REMOVED.

SITE MAP GENERAL NOTES

1. CONTRACTOR IS SOLELY RESPONSIBLE FOR SELECTION, IMPLEMENTATION, MAINTENANCE, AND EFFECTIVENESS OF ALL SWPPP CONTROLS - CONTROLS SHOWN ON THIS SITE MAP ARE SUGGESTED CONTROLS ONLY.
2. CONTRACTOR SHALL RECORD INSTALLATION, MAINTENANCE OR MODIFICATION, AND REMOVAL DATES FOR EACH BMP EMPLOYED (WHETHER CALLED OUT ON ORIGINAL SWPPP OR NOT) DIRECTLY ON THE SITE MAP.
3. TEMPORARY AND PERMANENT STABILIZATION PRACTICES AND BMP'S SHALL BE INSTALLED AT THE EARLIEST POSSIBLE TIME DURING THE CONSTRUCTION SEQUENCE. AS AN EXAMPLE, PERIMETER SILT FENCE SHALL BE INSTALLED IMMEDIATELY FOLLOWING COMPLETION OF GRADING ACTIVITIES. OTHER BMP'S SHALL BE INSTALLED AS SOON AS PRACTICABLE AND SHALL BE MAINTAINED UNTIL FINAL SITE STABILIZATION IS ATTAINED. CONTRACTOR SHALL ALSO REFERENCE CIVIL AND LANDSCAPE PLANS SINCE PERMANENT STABILIZATION IS PROVIDED BY LANDSCAPING, THE BUILDING(S), AND SITE PAVING.
4. BMP'S HAVE BEEN LOCATED AS INDICATED ON THIS PLAN IN ACCORDANCE WITH GENERALLY ACCEPTED ENGINEERING PRACTICES IN ORDER TO MINIMIZE SEDIMENT TRANSFER. FOR EXAMPLE, SILT FENCES LOCATED AT TOE OF SLOPE AND INLET PROTECTION FOR INLETS RECEIVING SEDIMENT FROM SITE RUN-OFF.
5. SANITARY SEWER EFFLUENT IS DISPOSED OF VIA AN ONSITE SEWER SYSTEM CONNECTED TO A MUNICIPAL SEWER SYSTEM.

STANDARD EROSION CONTROL GENERAL NOTES

1. EROSION CONTROL DEVICES SHOWN ON THIS PLAN SHALL BE INSTALLED PRIOR TO THE START OF LAND DISTURBING ACTIVITIES ON THE PROJECT
2. ALL EROSION CONTROL DEVICES ARE TO BE INSTALLED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS FOR THIS PROJECT. CHANGES ARE TO BE APPROVED BEFORE CONSTRUCTION BY THE DESIGN ENGINEER AND THE CITY ENGINEERING DIVISION.
3. IF THE EROSION CONTROL PLAN AS APPROVED CANNOT CONTROL EROSION AND OFF-SITE SEDIMENTATION FROM THE PROJECT, THE EROSION CONTROL PLAN WILL BE REQUIRED TO BE REVISED AND/OR ADDITIONAL EROSION CONTROL DEVICES WILL BE REQUIRED ON SITE.
4. INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STRORM EVENTS TO INSURE THAT THE DEVICES ARE FUNCTIONING PROPERLY. WHEN SEDIMENTATION OCCURS, THE DEVICES SHALL BE MAINTAINED. STONES OR MULCH BEING TRACKED ONTO A PUBLIC ROADWAY THE AGGREGATE PAD MUST BE WASHED DOWN OR REPLACED. RUNOFF FROM THE AGGREGATE PAD MUST BE COLLECTED AND DISCHARGED TO THE STREET DIRECTLY OR SITE WITHOUT FIRST FLOWING THROUGH ANOTHER BMP TO PREVENT THE SEDIMENTATION OF THE STREET. WHEN THE ADDITION OF NEW STONE MAY BE REQUIRED TO MAINTAIN THE EFFICIENCY OF THE INSTALLATION.
5. CONTRACTOR SHALL BE RESPONSIBLE FOR SUBMITTAL OF A N.O.I. N.O.T. AND ANY ADDITIONAL INFORMATION REQUIRED BY THE TCEQ WHEN THE PROJECT SHALL COME WITHIN 100 FEET OF A POTENTIAL POLLUTION PREVENTION REQUIREMENTS.

BMP MAINTENANCE SCHEDULE

TEMPORARY STONE CONSTRUCTION ENTRANCE/EXIT:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. AGGREGATE PAD SHALL BE WASHED DOWN OR REPLACED WHEN SEDIMENT OR MUD HAS CLOGGED THE VOID SPACES BETWEEN THE STONES OR MUD IS BEING TRACKED ONTO THE PUBLIC ROADWAY. RUNOFF FROM WASHDOWN OPERATION SHALL BE FILTERED THROUGH ANOTHER B.M.P. PRIOR TO DRAINING OFF-SITE.

SILT FENCE:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS. SEDIMENT SHALL BE REMOVED FROM BEHIND THE FENCE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-THIRD THE HEIGHT OF THE FENCE ABOVE GRADE. FENCE SHALL BE INSPECTED FOR GAPS AT BASE. INSPECT SUPPORTING POSTS AND FILTER FABRIC. REPLACE IF REQUIRED.

STONE OVERFLOW STRUCTURE:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. SEDIMENT SHALL BE REMOVED FROM THE STORAGE AREA WHEN SEDIMENT DEPTH HAS BUILT UP TO ONE-HALF THE HEIGHT OF THE STONE OUTLET. REPAIR DISLODGED OR MISSING STONE RIP-RAP AND REPAIR ANY DOWNSTREAM EROSION.

ROCK CHECK DAM:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA UPSTREAM OF THE DAM WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE DAM HEIGHT. REPAIR DAMAGE TO THE CHANNEL IN THE VICINITY OF THE CHECK DAMS IMMEDIATELY TO PREVENT ADDITIONAL DAMAGE. REPLACE MISSING OR DISLODGED ROCK AS NEEDED TO MAINTAIN THE DESIGN HEIGHT AND CROSS SECTION OF THE CHECK DAM.

CURB INLET/GRATE INLET/WYE INLET:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA SURROUNDING THE INLET/GRATE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE PROTECTION HEIGHT. DEVICE SHALL BE INSPECTED FOR GAPS AT BASE, AND SHALL BE REPLACED AS NEEDED.

VEGETATIVE STABILIZATION REQUIREMENTS

TEMPORARY SEEDING

ALL DISTURBED AREAS WHICH WILL BE LEFT DORMANT FOR GREATER THAN 14 DAYS SHALL BE SEEDED WITH FAST-GERMINATING TEMPORARY VEGETATION IMMEDIATELY FOLLOWING GRADING OPERATIONS. SELECTION OF THE SEED WILL DEPEND ON THE TIME OF YEAR IT IS APPLIED (SEE DESCRIPTIONS IN TABLE 2). REFERENCE LANDSCAPE PLAN FOR PERMANENT STABILIZATION REQUIREMENTS. ALL TEMPORARY SEEDING MATERIALS SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE PRIOR TO APPLICATION.

TABLE 2

TEMPORARY SEEDING		
SPECIES	PLANTING RATE	PLANTING DATES
CRIMSON CLOVER	7#/ACRE	8/15 - 11/30
MILLET, FOXTAIL	30#/ACRE	5/1 - 8/31
RYEGRASS, ANNUAL	30#/ACRE	8/15 - 9/30
SPRANGLETOP, GREEN	2.5#/ACRE	2/1 - 5/1
TALL FESCUE	7-10#/1000 SF	9/1 - 10/15

*USE ONLY USDA CERTIFIED SEED.

SURFACE PREPARATION FOR TEMPORARY SEEDING

1. INSTALL EROSION STRUCTURES SUCH AS DIKES, DIVERSIONS, ETC. PRIOR TO SEEDING.

2. FURROW SLOPES STEEPER THAN 3:1 ON THE CONTOUR LINE BEFORE SEEDING.

3. ENSURE SEED BED IS PULVERIZED, LOOSE, AND UNIFORM


APPLICATION

1. WHEN HYDROMULCHING IS USED, DO NOT MIX SEED AND FERTILIZER MORE THAN 30 MINUTES PRIOR TO APPLICATION.

2. APPLY SEED EVENLY USING PROPER EQUIPMENT AND WATER TO AID VEGETATION GROWTH.

3. EROSION CONTROL NETTING SHALL BE INSTALLED OVER FILL SLOPES WHICH HAVE BEEN BROUGHT TO FINAL GRADE AND HAVE BEEN SEED TO PROTECT AGAINST EROSION. MULCH (STRAW OR FIBER) SHALL BE USED ON RELATIVELY FLAT SLOPES.

Plotted By: Browning, Moson Date: June 11, 2025 08:40:46pm File Path: K:\Vrj_civil\063248015 - baker tract offsite sewer\CAD\plansheets\C-Eros.dwg
This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



EROSION CONTROL SCHEDULE AND PHASING

THE PROJECT SHALL GENERALLY CONFORM TO THE FOLLOWING:

PHASE A - GRADING

1. CONSTRUCT TEMPORARY CONSTRUCTION ENTRANCE, SILT FENCE, DIKE, AND TREE PROTECTION FENCE ACCORDING TO THE APPROXIMATE LOCATION AND SHOWN ON EROSION CONTROL PLAN NOTES AND DETAIL SHEET.
2. BEGIN CLEARING AND GRADING OF SITE.
3. SEED AND REVEGETATE SLOPES WHERE SHOWN.

PHASE B - UTILITIES

1. KEEP ALL STORM WATER POLLUTION PREVENTION MEASURES IN PLACE.
2. INSTALL STORM DRAINS, SANITARY SEWER, AND WATER AS SPECIFIED ON PLAN SHEETS.

PHASE C - LANDSCAPING AND SOIL STABILIZATION.

1. REVEGETATE LOT AND PARKWAYS
2. LANDSCAPE CONTRACTOR SHALL REVEGETATE ALL AREAS RESERVED FOR LANDSCAPE VEGETATIVE COVERS.
3. REMOVE EROSION CONTROL DEVICES WHEN MINIMUM 70% GROUND COVER IS ESTABLISHED.

VEGETATION MUST BE ESTABLISHED BEFORE STRUCTURAL CONTROLS REMOVED.

SITE MAP GENERAL NOTES

1. CONTRACTOR IS SOLELY RESPONSIBLE FOR SELECTION, IMPLEMENTATION, MAINTENANCE, AND EFFECTIVENESS OF ALL SWPPP CONTROLS - CONTROLS SHOWN ON THIS SITE MAP ARE SUGGESTED CONTROLS ONLY.
2. CONTRACTOR SHALL RECORD INSTALLATION, MAINTENANCE OR MODIFICATION, AND REMOVAL DATES FOR EACH BMP EMPLOYED (WHETHER CALLED OUT ON ORIGINAL SWPPP OR NOT) DIRECTLY ON THE SITE MAP.
3. TEMPORARY AND PERMANENT STABILIZATION PRACTICES AND BMP'S SHALL BE INSTALLED AT THE EARLIEST POSSIBLE TIME DURING THE CONSTRUCTION SEQUENCE. AS AN EXAMPLE, PERIMETER SILT FENCE SHALL BE INSTALLED BEFORE COMMENCEMENT OF ANY GRADING ACTIVITIES. OTHER BMP'S SHALL BE INSTALLED AS SOON AS PRACTICABLE AND SHALL BE MAINTAINED UNTIL FINAL SITE STABILIZATION IS ATTAINED. CONTRACTOR SHALL ALSO REFERENCE CIVIL AND LANDSCAPE PLANS SINCE PERMANENT STABILIZATION IS PROVIDED BY LANDSCAPING, THE BUILDING(S), AND SITE PAVING.
4. BMP'S HAVE BEEN LOCATED AS INDICATED ON THIS PLAN IN ACCORDANCE WITH GENERALLY ACCEPTED ENGINEERING PRACTICES IN ORDER TO MINIMIZE SEDIMENT TRANSFER. FOR EXAMPLE, SILT FENCES LOCATED AT TOE OF SLOPE AND INLET PROTECTION FOR INLETS RECEIVING SEDIMENT FROM SITE RUN-OFF.
5. SANITARY SEWER EFFLUENT IS DISPOSED OF VIA AN ONSITE SEWER SYSTEM CONNECTED TO A MUNICIPAL SEWER SYSTEM.

STANDARD EROSION CONTROL GENERAL NOTES

1. EROSION CONTROL DEVICES SHOWN ON THIS PLAN SHALL BE INSTALLED PRIOR TO THE START OF LAND DISTURBING ACTIVITIES ON THE PROJECT.
2. ALL EROSION CONTROL DEVICES ARE TO BE INSTALLED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS FOR THIS PROJECT. CHANGES ARE TO BE APPROVED BEFORE CONSTRUCTION BY THE DESIGN ENGINEER AND THE CITY ENGINEERING DIVISION.
3. IF THE EROSION CONTROL PLAN AS APPROVED CANNOT CONTROL EROSION AND OFF-SITE SEDIMENTATION FROM THE PROJECT, THE EROSION CONTROL PLAN WILL BE REQUIRED TO BE REVISED AND/OR ADDITIONAL EROSION CONTROL DEVICES WILL BE REQUIRED ON SITE.
4. INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO INSURE THAT THE DEVICES ARE FUNCTIONING PROPERLY. WHEN SEDIMENT OR MUD HAS CLOGGED THE VOID SPACES BETWEEN STONES OR MUD IS BEING TRACKED ONTO A PUBLIC ROADWAY THE AGGREGATE PAD MUST BE WASHED DOWN OR REPLACED. RUNOFF FROM THE WASHDOWN OPERATION SHALL NOT BE ALLOWED TO DRAIN DIRECTLY OFF SITE WITHOUT FIRST FLOWING THROUGH ANOTHER BMP TO CONTROL OFF SITE SEDIMENTATION. PERIODIC RE-GRADING OR THE ADDITION OF NEW STONE MAY BE REQUIRED TO MAINTAIN THE EFFICIENCY OF THE INSTALLATION.
5. CONTRACTOR SHALL BE RESPONSIBLE FOR SUBMITTAL OF N.O.I., N.O.T. AND ANY ADDITIONAL INFORMATION REQUIRED BY THE TCEQ. CONTRACTOR SHALL COMPLY WITH ALL TCEQ STORMWATER POLLUTION PREVENTION REQUIREMENTS.

BMP MAINTENANCE SCHEDULE

TEMPORARY STONE CONSTRUCTION ENTRANCE/EXIT:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. AGGREGATE PAD SHALL BE WASHED DOWN OR REPLACED WHEN SEDIMENT OR MUD HAS CLOGGED THE VOID SPACES BETWEEN THE STONES OR MUD IS BEING TRACKED ONTO THE PUBLIC ROADWAY. RUNOFF FROM WASHDOWN OPERATION SHALL BE FILTERED THROUGH ANOTHER B.M.P. PRIOR TO DRAINING OFF-SITE.

SILT FENCE:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS. SEDIMENT SHALL BE REMOVED FROM BEHIND THE FENCE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF THE HEIGHT OF THE FENCE ABOVE GRADE. FENCE SHALL BE INSPECTED FOR GAPS AT BASE. INSPECT SUPPORTING POSTS AND FILTER FABRIC. REPLACE IF REQUIRED.

STONE OVERFLOW STRUCTURE:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. SEDIMENT SHALL BE REMOVED FROM THE STORAGE AREA WHEN SEDIMENT DEPTH HAS BUILT UP TO ONE-HALF THE HEIGHT OF THE STONE OUTLET. REPAIR DISLODGED OR MISSING STONE RIP-RAP AND REPAIR ANY DOWNSTREAM EROSION.

ROCK CHECK DAM:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA UPSTREAM OF THE DAM WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE DAM HEIGHT. REPAIR DAMAGE TO THE CHANNEL IN THE VICINITY OF THE CHECK DAMS IMMEDIATELY TO PREVENT ADDITIONAL DAMAGE. REPLACE MISSING OR DISLODGED ROCK AS NEEDED TO MAINTAIN THE DESIGN HEIGHT AND CROSS SECTION OF THE CHECK DAM.

CURB INLET/GRATE INLET/WYVE INLET:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA SURROUNDING THE INLET/GRATE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE PROTECTION HEIGHT. DEVICE SHALL BE INSPECTED FOR GAPS AT BASE, AND SHALL BE REPLACED AS NEEDED.

VEGETATIVE STABILIZATION REQUIREMENTS

TEMPORARY SEEDING		
ALL DISTURBED AREAS WHICH WILL BE LEFT DORMANT FOR GREATER THAN 14 DAYS SHALL BE SEEDED WITH FAST-GERMINATING TEMPORARY VEGETATION IMMEDIATELY FOLLOWING GRADING OPERATIONS. SELECTION OF THE SEED WILL DEPEND ON THE TIME OF YEAR IT IS APPLIED (SEE DESCRIPTIONS IN TABLE 2). REFERENCE LANDSCAPE PLAN FOR PERMANENT STABILIZATION REQUIREMENTS. ALL TEMPORARY SEEDING MATERIALS SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE PRIOR TO APPLICATION.		
TABLE 2 VEGETATION TABLE*		
TEMPORARY SEEDING SPECIES	PLANTING RATE	PLANTING DATES
CRIMSON CLOVER	7#/ACRE	8/15 - 11/30
MILLET, FOXTAIL	30#/ACRE	9/1 - 9/31
RYEGRASS, ANNUAL	30#/ACRE	8/15 - 9/30
SPRANGLETOP, GREEN	25#/ACRE	2/1 - 5/1
TALL FESCUE	7#-10#/1000 SF	9/1 - 10/15

*USE ONLY USDA CERTIFIED SEED.

SURFACE PREPARATION FOR TEMPORARY SEEDING	
1. INSTALL EROSION STRUCTURES SUCH AS DIKES, DIVERSIONS, ETC. PRIOR TO SEEDING.	
2. FURROW SLOPES STEEPER THAN 3:1 ON THE CONTOUR LINE BEFORE SEEDING.	
3. ENSURE SEED BED IS PULVERIZED, LOOSE, AND UNIFORM.	

APPLICATION

1. WHEN HYDROMULCHING IS USED, DO NOT MIX SEED AND FERTILIZER MORE THAN 30 MINUTES PRIOR TO APPLICATION.
2. APPLY SEED EVENLY USING PROPER EQUIPMENT AND WATER TO AID VEGETATION GROWTH.
3. EROSION CONTROL NETTING SHALL BE INSTALLED OVER FILL SLOPES WHICH HAVE BEEN BROUGHT TO FINAL GRADE AND HAVE BEEN SEEDED TO PROTECT AGAINST EROSION. MULCH (STRAW OR FIBER) SHALL BE USED ON RELATIVELY FLAT SLOPES.

REVISIONS		DATE
No.		

Kimley»Horn
© 2025 KIMLEY-HORN AND ASSOCIATES, INC.
6180 WARREN PARKWAY, SUITE 210, FRISCO, TX 75034
PHONE: 972-335-3580
WWW.KIMLEY-HORN.COM
TEXAS REGISTERED ENGINEERING FIRM F-928


SCALE	DESIGNED BY	DRAWN BY	CHECKED BY
AS SHOWN	JNC	JNC	JTH

EROSION CONTROL PLAN

**BAKER TRACT
OFFSITE SEWER
CITY OF DENTON, TEXAS**

DATE	PROJECT NO.	SHEET NUMBER
06/11/25	063248015	C17.02

Plotted By: Browning, Moson Date: June 11, 2025 08:40:56pm File Path: K:\Vrj_civil\063248015 - baker tract offsite sewer\CAD\plansheets\C-Eros.dwg
This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



EROSION CONTROL
SCHEDULE AND PHASING

THE PROJECT SHALL GENERALLY CONFORM TO THE FOLLOWING:

PHASE A - GRADING
1. CONSTRUCT TEMPORARY CONSTRUCTION ENTRANCE, SILT FENCE, DIKE, AND TREE PROTECTION FENCE ACCORDING TO THE APPROXIMATE LOCATION AND SHOWN ON EROSION CONTROL PLAN NOTES AND DETAIL SHEET.
2. BEGIN CLEARING AND GRADING OF SITE.
3. SEED AND REVEGETATE SLOPES WHERE SHOWN.

PHASE B - UTILITIES
1. KEEP ALL STORM WATER POLLUTION PREVENTION MEASURES IN PLACE.
2. INSTALL STORM DRAINS, SANITARY SEWER, AND WATER AS SPECIFIED ON PLAN SHEETS.

PHASE C - LANDSCAPING AND SOIL STABILIZATION.
1. REVEGETATE LOT AND PARKWAYS
2. LANDSCAPE CONTRACTOR SHALL REVEGETATE ALL AREAS RESERVED FOR LANDSCAPE VEGETATIVE COVERS.
3. REMOVE EROSION CONTROL DEVICES WHEN MINIMUM 70% GROUND COVER IS ESTABLISHED.
VEGETATION MUST BE ESTABLISHED BEFORE STRUCTURAL CONTROLS REMOVED.

SITE MAP GENERAL NOTES

1. CONTRACTOR IS SOLELY RESPONSIBLE FOR SELECTION, IMPLEMENTATION, MAINTENANCE, AND EFFECTIVENESS OF ALL SWPPP CONTROLS - CONTROLS SHOWN ON THIS SITE MAP ARE SUGGESTED CONTROLS ONLY.

2. CONTRACTOR SHALL RECORD INSTALLATION, MAINTENANCE OR MODIFICATION, AND REMOVAL DATES FOR EACH BMP EMPLOYED (WHETHER CALLED OUT ON ORIGINAL SWPPP OR NOT) DIRECTLY ON THE SITE MAP.

3. TEMPORARY AND PERMANENT STABILIZATION PRACTICES AND BMP'S SHALL BE INSTALLED AT THE EARLIEST POSSIBLE TIME DURING THE CONSTRUCTION SEQUENCE. AS AN EXAMPLE, PERIMETER SILT FENCE SHALL BE INSTALLED BEFORE COMMENCEMENT OF ANY GRADING ACTIVITIES. OTHER BMP'S SHALL BE INSTALLED AS SOON AS PRACTICABLE AND SHALL BE MAINTAINED UNTIL FINAL SITE STABILIZATION IS ATTAINED. CONTRACTOR SHALL ALSO REFERENCE CIVIL AND LANDSCAPE PLANS SINCE PERMANENT STABILIZATION IS PROVIDED BY LANDSCAPING, THE BUILDING(S), AND SITE PAVING.

4. BMP'S HAVE BEEN LOCATED AS INDICATED ON THIS PLAN IN ACCORDANCE WITH GENERALLY ACCEPTED ENGINEERING PRACTICES IN ORDER TO MINIMIZE SEDIMENT TRANSFER. FOR EXAMPLE, SILT FENCES LOCATED AT TOE OF SLOPE AND INLET PROTECTION FOR INLETS RECEIVING SEDIMENT FROM SITE RUN-OFF.

5. SANITARY SEWER EFFLUENT IS DISPOSED OF VIA AN ONSITE SEWER SYSTEM CONNECTED TO A MUNICIPAL SEWER SYSTEM.

STANDARD EROSION CONTROL
GENERAL NOTES

1. EROSION CONTROL DEVICES SHOWN ON THIS PLAN SHALL BE INSTALLED PRIOR TO THE START OF LAND DISTURBING ACTIVITIES ON THE PROJECT.

2. ALL EROSION CONTROL DEVICES ARE TO BE INSTALLED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS FOR THIS PROJECT. CHANGES ARE TO BE APPROVED BEFORE CONSTRUCTION BY THE DESIGN ENGINEER AND THE CITY ENGINEERING DIVISION.

3. IF THE EROSION CONTROL PLAN AS APPROVED CANNOT CONTROL EROSION AND OFF-SITE SEDIMENTATION FROM THE PROJECT, THE EROSION CONTROL PLAN WILL BE REQUIRED TO BE REVISED AND/OR ADDITIONAL EROSION CONTROL DEVICES WILL BE REQUIRED ON SITE.

4. INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO INSURE THAT THE DEVICES ARE FUNCTIONING PROPERLY. WHEN SEDIMENT OR MUD HAS CLOGGED THE VOID SPACES BETWEEN STONES OR MUD IS BEING TRACKED ONTO A PUBLIC ROADWAY THE AGGREGATE PAD MUST BE WASHED DOWN OR REPLACED. RUNOFF FROM THE WASHDOWN OPERATION SHALL NOT BE ALLOWED TO DRAIN DIRECTLY OFF SITE WITHOUT FIRST FLOWING THROUGH ANOTHER BMP TO CONTROL OFF SITE SEDIMENTATION. PERIODIC RE-GRADING OR THE ADDITION OF NEW STONE MAY BE REQUIRED TO MAINTAIN THE EFFICIENCY OF THE INSTALLATION.

5. CONTRACTOR SHALL BE RESPONSIBLE FOR SUBMITTAL OF N.O.I., N.O.T. AND ANY ADDITIONAL INFORMATION REQUIRED BY THE TCEQ ACCORDING TO THE TCEQ STORMWATER POLLUTION PREVENTION REQUIREMENTS.

BMP MAINTENANCE SCHEDULE

TEMPORARY STONE CONSTRUCTION ENTRANCE/EXIT:
INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. AGGREGATE PAD SHALL BE WASHED DOWN OR REPLACED WHEN SEDIMENT OR MUD HAS CLOGGED THE VOID SPACES BETWEEN THE STONES OR MUD IS BEING TRACKED ONTO THE PUBLIC ROADWAY. RUNOFF FROM WASHDOWN OPERATION SHALL BE FILTERED THROUGH ANOTHER B.M.P. PRIOR TO DRAINING OFF-SITE.

SILT FENCE:
INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS. SEDIMENT SHALL BE REMOVED FROM BEHIND THE FENCE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF THE HEIGHT OF THE FENCE ABOVE GRADE. FENCE SHALL BE INSPECTED FOR GAPS AT BASE. INSPECT SUPPORTING POSTS AND FILTER FABRIC. REPLACE IF REQUIRED.

STONE OVERFLOW STRUCTURE:
INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. SEDIMENT SHALL BE REMOVED FROM THE STORAGE AREA WHEN SEDIMENT DEPTH HAS BUILT UP TO ONE-HALF THE HEIGHT OF THE STONE OUTLET. REPAIR DISLODGED OR MISSING STONE RIP-RAP AND REPAIR ANY DOWNSTREAM EROSION.

ROCK CHECK DAM:
INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA UPSTREAM OF THE DAM WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE DAM HEIGHT. REPAIR DAMAGE TO THE CHANNEL IN THE VICINITY OF THE CHECK DAMS IMMEDIATELY TO PREVENT ADDITIONAL DAMAGE. REPLACE MISSING OR DISLODGED ROCK AS NEEDED TO MAINTAIN THE DESIGN HEIGHT AND CROSS SECTION OF THE CHECK DAM.

CURB INLET/GRATE INLET/WYVE INLET:
INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA SURROUNDING THE INLET/GRATE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE PROTECTION HEIGHT. DEVICE SHALL BE INSPECTED FOR GAPS AT BASE, AND SHALL BE REPLACED AS NEEDED.

VEGETATIVE STABILIZATION REQUIREMENTS

TEMPORARY SEEDING
ALL DISTURBED AREAS WHICH WILL BE LEFT DORMANT FOR GREATER THAN 14 DAYS SHALL BE SEED WITH FAST-GERMINATING TEMPORARY VEGETATION IMMEDIATELY FOLLOWING GRADING OPERATIONS. SELECTION OF THE SEED WILL DEPEND ON THE TIME OF YEAR IT IS APPLIED (SEE DESCRIPTIONS IN TABLE 2). REFERENCE LANDSCAPE PLAN FOR PERMANENT STABILIZATION REQUIREMENTS. ALL TEMPORARY SEEDING MATERIALS SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE PRIOR TO APPLICATION.

TABLE 2
VEGETATION TABLE*
TEMPORARY SEEDING
SPECIES PLANTING RATE PLANTING DATES
CRIMSON CLOVER 7#/ACRE 8/15 - 11/30
MILLET, FOXTAIL 30#/ACRE 9/1 - 9/31
RYEGRASS, ANNUAL 30#/ACRE 8/15 - 9/30
SPRANGLETOP, GREEN 25#/ACRE 2/1 - 5/1
TALL FESCUE 7#-10#/1000 SF 9/1 - 10/15
*USE ONLY USDA CERTIFIED SEED.

SURFACE PREPARATION FOR TEMPORARY SEEDING
1. INSTALL EROSION STRUCTURES SUCH AS DIKES, DIVERSIONS, ETC. PRIOR TO SEEDING.
2. FURROW SLOPES STEEPER THAN 3:1 ON THE CONTOUR LINE BEFORE SEEDING.
3. ENSURE SEED BED IS PULVERIZED, LOOSE, AND UNIFORM.

APPLICATION
1. WHEN HYDROMULCHING IS USED, DO NOT MIX SEED AND FERTILIZER MORE THAN 30 MINUTES PRIOR TO APPLICATION.
2. APPLY SEED EVENLY USING PROPER EQUIPMENT AND WATER TO AID VEGETATION GROWTH.
3. EROSION CONTROL NETTING SHALL BE INSTALLED OVER FILL SLOPES WHICH HAVE BEEN BROUGHT TO FINAL GRADE AND HAVE BEEN SEEDDED TO PROTECT AGAINST EROSION. MULCH (STRAW OR FIBER) SHALL BE USED ON RELATIVELY FLAT SLOPES.

BAKER TRACT
OFFSITE SEWER
CITY OF DENTON, TEXAS

DATE
06/11/25

PROJECT NO.
063248015

SHEET NUMBER
C17.03



Kimley»Horn
© 2025 KIMLEY-HORN AND ASSOCIATES, INC.
6180 WARREN PARKWAY, SUITE 210, FRISCO, TX 75034
PHONE: 972-335-3580
WWW.KIMLEY-HORN.COM
TEXAS REGISTERED ENGINEERING FIRM F-928

STATE OF TEXAS
JOHN HALE
145933
LICENSED PROFESSIONAL ENGINEER
06/17/2025

SCALE
AS SHOWN
DESIGNED BY
JNC
DRAWN BY
JNC
CHECKED BY
JTH


EROSION CONTROL PLAN

REVISIONS
No.
DATE



GRAPHIC SCALE IN FEET

LEGEND



EROSION CONTROL SCHEDULE AND PHASING

THE PROJECT SHALL GENERALLY CONFORM TO THE FOLLOWING

- PHASE A - GRADING
1. CONSTRUCT TEMPORARY CONSTRUCTION ENTRANCE, SILT FENCE, DIKE, AND TREE PROTECTION FENCE ACCORDING TO THE APPROXIMATE LOCATION AND SHOWN ON EROSION CONTROL PLAN NOTES AND DETAIL SHEET.
 2. BEGIN CLEARING AND GRADING OF SITE.
 3. SEED AND REVEGETATE SLOPES WHERE SHOWN.

- PHASE B - UTILITIES
1. KEEP ALL STORM WATER POLLUTION PREVENTION MEASURES IN PLACE.
 2. INSTALL STORM DRAINS, SANITARY SEWER, AND WATER AS SPECIFIED ON PLAN SHEETS.

- PHASE C - LANDSCAPING AND SOIL STABILIZATION.
1. REVEGETATE LOT AND PARKWAYS
2. LANDSCAPE CONTRACTOR SHALL REVEGETATE ALL AREAS RESERVED FOR LANDSCAPE VEGETATIVE COVERS.
3. REMOVE EROSION CONTROL DEVICES WHEN MINIMUM 70% GROUND COVER IS ESTABLISHED.
- VEGETATION MUST BE ESTABLISHED BEFORE STRUCTURAL CONTROLS REMOVED.

SITE MAP GENERAL NOTES

1. CONTRACTOR IS SOLELY RESPONSIBLE FOR SELECTION, IMPLEMENTATION MAINTENANCE, AND EFFECTIVENESS OF ALL SWPPP CONTROLS - CONTROL SHOWN ON THIS SITE MAP ARE SUGGESTED CONTROLS ONLY.
2. CONTRACTOR SHALL RECORD INSTALLATION, MAINTENANCE OR MODIFICATION, AND REMOVAL DATES FOR EACH BMP EMPLOYED (WHETHER CALLED OUT ON ORIGINAL SWPPP OR NOT) DIRECTLY ON THE SITE MAP.
3. TEMPORARY AND PERMANENT STABILIZATION PRACTICES AND BMPs SHALL BE INSTALLED AT THE EARLIEST POSSIBLE TIME DURING THE CONSTRUCTION SEQUENCE. AS AN EXAMPLE, PERIMETER SILT FENCE SHALL BE INSTALLED IMMEDIATELY FOLLOWING COMPLETION OF ANY GRADING ACTIVITIES. OTHER BMPs SHALL BE INSTALLED AS SOON AS PRACTICABLE AND SHALL BE MAINTAINED UNTIL FINAL SITE STABILIZATION IS ATTAINED. CONTRACTOR SHALL ALSO REFERENCE CIVIL AND LANDSCAPE PLANS SINCE PERMANENT STABILIZATION IS PROVIDED BY LANDSCAPING, THE BUILDING(S), AND SITE PAVING.
4. BMPs HAVE BEEN LOCATED AS INDICATED ON THIS PLAN IN ACCORDANCE WITH GENERALLY ACCEPTED ENGINEERING PRACTICES IN ORDER TO MINIMIZE SEDIMENT TRANSFER FOR EXAMPLE, SILT FENCES LOCATED AT TOE OF SLOPE AND INLET PROTECTION FOR INLETS RECEIVING SEDIMENT FROM SITE RUN-OFF.
5. SANITARY SEWER EFFLUENT IS DISPOSED OF VIA AN ONSITE SEWER SYSTEM CONNECTED TO A MUNICIPAL SEWER SYSTEM.

STANDARD EROSION CONTROL GENERAL NOTES

1. EROSION CONTROL DEVICES SHOWN ON THIS PLAN SHALL BE INSTALLED PRIOR TO THE START OF LAND DISTURBING ACTIVITIES ON THE PROJECT.
2. ALL EROSION CONTROL DEVICES ARE TO BE INSTALLED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS FOR THIS PROJECT. CHANGES ARE TO BE APPROVED BEFORE CONSTRUCTION BY THE DESIGN ENGINEER AND THE CITY ENGINEERING DIVISION.
3. IF THE EROSION CONTROL PLAN AS APPROVED CANNOT CONTROL EROSION AND OFF-SITE SEDIMENTATION FROM THE PROJECT, THE EROSION CONTROL PLAN WILL BE REQUIRED TO BE REVISED AND/OR ADDITIONAL EROSION CONTROL DEVICES WILL BE REQUIRED ON SITE.
4. INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO INSURE THAT THE DEVICES ARE FUNCTIONING PROPERLY. WHEN A DEVICES IS DAMAGED OR WHEN EROSION OCCURS IN STONES OR MULCH IS BEING TRACKED ONTO A PUBLIC ROADWAY THE AGGREGATE PAVED SURFACE SHALL BE WASHED DOWN OR REPLACED. RUNOFF FROM THE CONSTRUCTION MATERIALS STORAGE AREA SHALL NOT BE ALLOWED TO DIRECTLY OFF SITE WITHOUT FIRST FLOWING THROUGH ANOTHER BMP TO PREVENT EROSION AND SEDIMENTATION. PERMITS FOR THE ADDITION OF NEW STONE MAY BE REQUIRED TO MAINTAIN THE EROSION OF THE INSTALLATION.
5. CONTRACTOR SHALL BE RESPONSIBLE FOR SUBMITTAL OF N.O.I. N.O.T. AND ANY ADDITIONAL INFORMATION REQUIRED BY THE TCEQ TO OBTAIN A CONSTRUCTION PERMIT FOR THE STORMWATER POLLUTION PREVENTION REQUIREMENTS.

BMP MAINTENANCE SCHEDULE

TEMPORARY STONE CONSTRUCTION ENTRANCE/EXIT:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. AGGREGATE PAD SHALL BE WASHED DOWN OR REPLACED WHEN SEDIMENT OR MUD HAS CLOGGED THE VOID SPACES BETWEEN THE STONES OR MUD IS BEING TRACKED ONTO THE PUBLIC ROADWAY. RUNOFF FROM WASHDOWN OPERATION SHALL BE FILTERED THROUGH ANOTHER B.M.P. PRIOR TO DRAINING OFF-SITE.

SILT FENCE:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS. SEDIMENT SHALL BE REMOVED FROM BEHIND THE FENCE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-THIRD THE HEIGHT OF THE FENCE ABOVE GRADE. FENCE SHALL BE INSPECTED FOR GAPS AT BASE. INSPECT SUPPORTING POSTS AND FILTER FABRIC. REPLACE IF REQUIRED.

STONE OVERFLOW STRUCTURE:

STONE OVERFLOW STRUCTURE:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. SEDIMENT SHALL BE REMOVED FROM THE STORAGE AREA WHEN SEDIMENT DEPTH HAS BUILT UP TO ONE-HALF THE HEIGHT OF THE STONE OUTLET. REPAIR DISLODGED OR MISSING STONE RIP-RAP AND REPAIR ANY DOWNSTREAM EROSION.

ROCK CHECK DAM:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA UPSTREAM OF THE DAM WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE DAM HEIGHT. REPAIR DAMAGE TO THE CHANNEL IN THE VICINITY OF THE CHECK DAMS IMMEDIATELY TO PREVENT ADDITIONAL DAMAGE. REPLACE MISSING OR DISLODGED ROCK AS NEEDED TO MAINTAIN THE DESIGN HEIGHT AND CROSS SECTION OF THE CHECK DAM.

CURB INLET/GRATE INLET/WYE INLET:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA SURROUNDING THE INLET/GRATE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE PROTECTION HEIGHT. DEVICE SHALL BE INSPECTED FOR GAPS AT BASE, AND SHALL BE REPLACED AS NEEDED.

VEGETATIVE STABILIZATION REQUIREMENTS

TEMPORARY SEEDING

ALL DISTURBED AREAS WHICH WILL BE LEFT DORMANT FOR GREATER THAN 14 DAYS SHALL BE SEEDED WITH FAST-GERMINATING TEMPORARY VEGETATION IMMEDIATELY FOLLOWING GRADING OPERATIONS. SELECTION OF THE SEED WILL DEPEND ON THE TIME OF YEAR IT IS APPLIED (SEE DESCRIPTIONS IN TABLE 2). REFERENCE LANDSCAPE PLAN FOR PERMANENT STABILIZATION REQUIREMENTS. ALL TEMPORARY SEEDING MATERIALS SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE PRIOR TO APPLICATION.

TABLE 2
VEGETATION TABLE

TEMPORARY SEEDING		
<u>SPECIES</u>	<u>PLANTING RATE</u>	<u>PLANTING DATES</u>
CRIMSON CLOVER	7#/ACRE	8/15 - 11/30
MILLET, FOXTAIL	30#/ACRE	5/1 - 8/31
RYEGRASS, ANNUAL	30#/ACRE	8/15 - 9/30
SPRANGLETOP, GREEN	2.5#/ACRE	2/1 - 5/1
TALL FESCUE	7#-10#/1000 SF	9/1 - 10/15

*USE ONLY USDA CERTIFIED SEED.

SURFACE PREPARATION FOR TEMPORARY SEEDING

1. INSTALL EROSION STRUCTURES SUCH AS DIKES, DIVERSIONS, ETC. PRIOR TO SEEDING.

2. FURROW SLOPES STEEPER THAN 3:1 ON THE CONTOUR LINE BEFORE SEEDING.



3. ENSURE SEED BED IS PULVERIZED, LOOSE, AND UNIFORM

APPLICATION

1. WHEN HYDROMULCHING IS USED, DO NOT MIX SEED AND FERTILIZER MORE THAN 30 MINUTES PRIOR TO APPLICATION.

2. APPLY SEED EVENLY USING PROPER EQUIPMENT AND WATER TO AID VEGETATION GROWTH.

3. EROSION CONTROL NETTING SHALL BE INSTALLED OVER FILL SLOPES WHICH HAVE BEEN BROUGHT TO FINAL GRADE AND HAVE BEEN SEED TO PROTECT AGAINST EROSION. MULCH (STRAW OR FIBER) SHALL BE USED ON RELATIVELY FLAT SLOPES.



EROSION CONTROL SCHEDULE AND PHASING

THE PROJECT SHALL GENERALLY CONFORM TO THE FOLLOWING:

PHASE A - GRADING

1. CONSTRUCT TEMPORARY CONSTRUCTION ENTRANCE, SILT FENCE, DIKE AND TREE PROTECTION FENCE ACCORDING TO THE APPROXIMATE LOCATION AND SHOWN ON EROSION CONTROL PLAN NOTES AND DETAIL SHEET.
2. BEGIN CLEARING AND GRADING OF SITE.
3. SEED AND REVEGETATE SLOPES WHERE SHOWN.

PHASE B - UTILITIES

1. KEEP ALL STORM WATER POLLUTION PREVENTION MEASURES IN PLACE.
2. KEEP ALL STORM DRAINS, SANITARY SEWER, AND WATER AS SPECIFIED ON PLAN SHEETS.

PHASE C - LANDSCAPING AND SOIL STABILIZATION

1. REVEGETATE LOT C AND PARKWAYS.
2. LANDSCAPE CONTRACTOR SHALL REVEGETATE ALL AREAS RESERVED FOR LANDSCAPE VEGETATIVE COVERS.
3. REMOVE EROSION CONTROL DEVICES WHEN MINIMUM 70% GROUND COVER IS ESTABLISHED.

VEGETATION MUST BE ESTABLISHED BEFORE STRUCTURAL CONTROLS REMOVED.

SITE MAP GENERAL NOTES

1. CONTRACTOR IS SOLELY RESPONSIBLE FOR SELECTION, IMPLEMENTATION, MAINTENANCE, AND EFFECTIVENESS OF ALL SWPPP CONTROLS - CONTROLS SHOWN ON THIS SITE MAP ARE SUGGESTED CONTROLS ONLY.
2. CONTRACTOR SHALL RECORD INSTALLATION, MAINTENANCE OR MODIFICATION, AND REMOVAL DATES FOR EACH BMP EMPLOYED (WHETHER CALLED OUT ON ORIGINAL SWPPP OR NOT) DIRECTLY ON THE SITE MAP.
3. TEMPORARY AND PERMANENT STABILIZATION PRACTICES AND BMP'S SHALL BE INSTALLED AT THE EARLIEST POSSIBLE TIME DURING THE CONSTRUCTION SEQUENCE. AS AN EXAMPLE, PERIMETER SILT FENCE SHALL BE INSTALLED BEFORE COMMENCEMENT OF ANY GRADING ACTIVITIES. OTHER GRADING ACTIVITIES SHALL BE CONSIDERED PRACTICABLE AND SHALL BE MAINTAINED UNTIL FINAL SITE STABILIZATION IS ATTAINED. CONTRACTOR SHALL ALSO REFERENCE CIVIL AND LANDSCAPE PLANS SINCE PERMANENT STABILIZATION IS PROVIDED BY LANDSCAPING, THE BUILDING(S), AND SITE PAVING.
4. BMP'S HAVE BEEN LOCATED AS INDICATED ON THIS PLAN IN ACCORDANCE WITH GENERALLY ACCEPTED ENGINEERING PRACTICES IN ORDER TO MINIMIZE EROSION AND TRANSPORT. FOR EXAMPLE, SILT FENCES LOCATED AT TOE OF SLOPE AND INLET PROTECTION FOR INLETS RECEIVING SEDIMENT FROM SITE RUN-OFF.
5. SANITARY SEWER EFFLUENT IS DISPOSED OF VIA AN ONSITE SEWER SYSTEM CONNECTED TO A MUNICIPAL SEWER SYSTEM.

STANDARD EROSION CONTROL GENERAL NOTES

1. EROSION CONTROL DEVICES SHOWN ON THIS PLAN SHALL BE INSTALLED PRIOR TO THE START OF LAND DISTURBING ACTIVITIES ON THE PROJECT.
2. ALL EROSION CONTROL DEVICES ARE TO BE INSTALLED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS FOR THIS PROJECT. CHANGES ARE TO BE APPROVED BEFORE CONSTRUCTION BY THE DESIGN ENGINEER AND THE CITY ENGINEERING DIVISION.
3. IF THE EROSION CONTROL PLAN AS APPROVED CANNOT CONTROL EROSION AND OFF-SITE SEDIMENTATION FROM THE PROJECT, THE EROSION CONTROL PLAN WILL BE REQUIRED TO BE REVISED AND/OR ADDITIONAL EROSION CONTROL DEVICES WILL BE REQUIRED ON SITE.
4. INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO INSURE THAT THE DEVICES ARE FUNCTIONING PROPER. WHEN SEDIMENTATION OCCURS, THE DEVICES SHALL BE MAINTAINED OR RUMD IS BEING TRACKED ONTO A PUBLIC ROADWAY THE AGGREGATE PAD MUST BE WASHED DOWN OR REPLACED. RUNOFF FROM THE AGGREGATE PAD SHALL NOT BE ALLOWED TO ENTER THE STREET. DIRECTLY OFF SITE WITHOUT FIRST FLOWING THROUGH ANOTHER BMP OR CONSTRUCTED OFF SITE SEDIMENTATION. PERIODIC REPAIRING OF THE DEVICES SHALL BE REQUIRED TO MAINTAIN EFFICIENCY OF THE INSTALLATION.
5. CONTRACTOR SHALL BE RESPONSIBLE FOR SUBMITTAL OF NO I, N.O.T. AND ANY ADDITIONAL INFORMATION REQUIRED BY THE TCEQ TO OBTAIN A CONSTRUCTION PERMIT FOR THE STORMWATER POLLUTION PREVENTION REQUIREMENTS.

BMP MAINTENANCE SCHEDULE

TEMPORARY STONE CONSTRUCTION ENTRANCE/EXIT:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. AGGREGATE PAD SHALL BE WASHED DOWN OR REPLACED WHEN SEDIMENT OR MUD HAS CLOGGED THE VOID SPACES BETWEEN THE STONES OR MUD IS BEING TRACKED ONTO THE PUBLIC ROADWAY. RUNOFF FROM WASHDOWN OPERATION SHALL BE FILTERED THROUGH ANOTHER B.M.P. PRIOR TO DRAINING OFF-SITE.

SILT FENCE:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS. SEDIMENT SHALL BE REMOVED FROM BEHIND THE FENCE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-THIRD THE HEIGHT OF THE FENCE ABOVE GRADE. FENCE SHALL BE INSPECTED FOR GAPS AT BASE, INSPECT SUPPORTING POSTS AND FILTER FABRIC. REPLACE IF REQUIRED.

STONE OVERFLOW STRUCTURE

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. SEDIMENT SHALL BE REMOVED FROM THE STORAGE AREA WHEN SEDIMENT DEPTH HAS BUILT UP TO ONE-HALF THE HEIGHT OF THE STONE OUTLET. REPAIR DISLODGED OR MISSING STONE RIP-RAP AND REPAIR ANY DOWNSTREAM EROSION.

ROCK CHECK DAM:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA UPSTREAM OF THE DAM WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE DAM HEIGHT. REPAIR DAMAGE TO THE CHANNEL IN THE VICINITY OF THE CHECK DAMS IMMEDIATELY TO PREVENT ADDITIONAL DAMAGE. REPLACE MISSING OR DISLODGED ROCK AS NEEDED TO MAINTAIN THE DESIGN HEIGHT AND CROSS SECTION OF THE CHECK DAM.

CURB INLET/GRATE INLET/WYE INLET:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA SURROUNDING THE INLET/GRATE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE PROTECTION HEIGHT. DEVICE SHALL BE INSPECTED FOR GAPS AT BASE, AND SHALL BE REPLACED AS NEEDED.

VEGETATIVE STABILIZATION REQUIREMENTS

TEMPORARY SEEDING

ALL DISTURBED AREAS WHICH WILL BE LEFT DORMANT FOR GREATER THAN 14 DAYS SHALL BE SEEDED WITH FAST-GERMINATING TEMPORARY VEGETATION IMMEDIATELY FOLLOWING GRADING OPERATIONS. SELECTION OF THE SEED WILL DEPEND ON THE TIME OF YEAR IT IS APPLIED (SEE DESCRIPTIONS IN TABLE 2). REFERENCE LANDSCAPE PLAN FOR PERMANENT STABILIZATION REQUIREMENTS. ALL TEMPORARY SEEDING MATERIALS SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE PRIOR TO APPLICATION.

SURFACE PREPARATION FOR TEMPORARY SEEDING

1. INSTALL EROSION STRUCTURES SUCH AS DIKES, DIVERSIONS, ETC. PRIOR TO SEEDING.

2. FURROW SLOPES STEEPER THAN 3:1 ON THE CONTOUR LINE BEFORE SEEDING.

APPLICATION


1. WHEN HYDROMULCHING IS USED, DO NOT MIX SEED AND FERTILIZER MORE THAN 30 MINUTES PRIOR TO APPLICATION.

2. APPLY SEED EVENLY USING PROPER EQUIPMENT AND WATER TO A VEGETATION GROWTH.

3. EROSION CONTROL NETTING SHALL BE INSTALLED OVER FILL SLOPES WHICH HAVE BEEN BROUGHT TO FINAL GRADE AND HAVE BEEN SEED TO PROTECT AGAINST EROSION. MULCH (STRAW OR FIBER) SHALL BE USED ON RELATIVELY FLAT SLOPES.


TEMPORARY SEEDING		
SPECIES	PLANTING RATE	PLANTING DATES
CRIMSON CLOVER	7#/ACRE	8/15 - 11/30
MILLET, FOXTAIL	30#/ACRE	5/1 - 8/31
RYEGRASS, ANNUAL	30#/ACRE	8/15 - 9/30
SPRANGLETOP, GREEN	2.5#/ACRE	2/1 - 5/1
TALL FESCUE	7#-10#/1000 SF	9/1 - 10/15

*USE ONLY USDA CERTIFIED SEED

C17.05	SHEET NUMBER	BAKER TRACT OFFSITE SEWER CITY OF DENTON, TEXAS	EROSION CONTROL PLAN	SCALE AS SHOWN DESIGNED BY JKH DRAWN BY JKH JNC CHECKED BY JTH		Kimley»»Horn © 2025 KIMLEY-HORN AND ASSOCIATES, INC. 6100 WARREN PARKWAY, SUITE 200, ARLING, TX 76010 PHONE: 972-335-3590 WWW.KIMLEY-HORN.COM TEXAS REGISTERED ENGINEERING FIRM F-428	No.	REVISIONS	DATE
	PROJECT NO. 063248015								

Plotted By: Browning, Moson Date: June 11, 2025 08:41:25am File Path: K:\VrL\civil\063248015 - baker tract offsite sewer\CAD\plansheets\C-Eros.dwg

This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



EROSION CONTROL SCHEDULE AND PHASING

THE PROJECT SHALL GENERALLY CONFORM TO THE FOLLOWING:

PHASE A - GRADING

1. CONSTRUCT TEMPORARY CONSTRUCTION ENTRANCE, SILT FENCE, DIKE, AND TREE PROTECTION FENCE ACCORDING TO THE APPROXIMATE LOCATION AND SHOWN ON EROSION CONTROL PLAN NOTES AND DETAIL SHEET.

2. BEGIN CLEARING AND GRADING OF SITE.

3. SEED AND REVEGETATE SLOPES WHERE SHOWN.

PHASE B - UTILITIES

1. KEEP ALL STORM WATER POLLUTION PREVENTION MEASURES IN PLACE.

2. INSTALL STORM DRAINS, SANITARY SEWER, AND WATER AS SPECIFIED ON PLAN SHEETS.

PHASE C - LANDSCAPING AND SOIL STABILIZATION.

1. REVEGETATE LOT AND PARKWAYS

2. LANDSCAPE CONTRACTOR SHALL REVEGETATE ALL AREAS RESERVED FOR LANDSCAPE VEGETATIVE COVERS.

3. REMOVE EROSION CONTROL DEVICES WHEN MINIMUM 70% GROUND COVER IS ESTABLISHED.

VEGETATION MUST BE ESTABLISHED BEFORE STRUCTURAL CONTROLS REMOVED.

SITE MAP GENERAL NOTES

1. CONTRACTOR IS SOLELY RESPONSIBLE FOR SELECTION, IMPLEMENTATION, MAINTENANCE, AND EFFECTIVENESS OF ALL SWPPP CONTROLS - CONTROLS SHOWN ON THIS SITE MAP ARE SUGGESTED CONTROLS ONLY.

2. CONTRACTOR SHALL RECORD INSTALLATION, MAINTENANCE OR MODIFICATION, AND REMOVAL DATES FOR EACH BMP EMPLOYED (WHETHER CALLED OUT ON ORIGINAL SWPPP OR NOT) DIRECTLY ON THE SITE MAP.

3. TEMPORARY AND PERMANENT STABILIZATION PRACTICES AND BMP'S SHALL BE INSTALLED AT THE EARLIEST POSSIBLE TIME DURING THE CONSTRUCTION SEQUENCE. AS AN EXAMPLE, PERIMETER SILT FENCE SHALL BE INSTALLED BEFORE COMMENCEMENT OF ANY GRADING ACTIVITIES. OTHER BMP'S SHALL BE INSTALLED AS SOON AS PRACTICABLE AND SHALL BE MAINTAINED UNTIL FINAL SITE STABILIZATION IS ATTAINED. CONTRACTOR SHALL ALSO REFERENCE CIVIL AND LANDSCAPE PLANS SINCE PERMANENT STABILIZATION IS PROVIDED BY LANDSCAPING, THE BUILDING(S), AND SITE PAVING.

4. BMP'S HAVE BEEN LOCATED AS INDICATED ON THIS PLAN IN ACCORDANCE WITH GENERALLY ACCEPTED ENGINEERING PRACTICES IN ORDER TO MINIMIZE SEDIMENT TRANSFER. FOR EXAMPLE, SILT FENCES LOCATED AT TOE OF SLOPE AND INLET PROTECTION FOR INLETS RECEIVING SEDIMENT FROM SITE RUN-OFF.

5. SANITARY SEWER EFFLUENT IS DISPOSED OF VIA AN ONSITE SEWER SYSTEM CONNECTED TO A MUNICIPAL SEWER SYSTEM.

STANDARD EROSION CONTROL GENERAL NOTES

1. EROSION CONTROL DEVICES SHOWN ON THIS PLAN SHALL BE INSTALLED PRIOR TO THE START OF LAND DISTURBING ACTIVITIES ON THE PROJECT.

2. ALL EROSION CONTROL DEVICES ARE TO BE INSTALLED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS FOR THIS PROJECT. CHANGES ARE TO BE APPROVED BEFORE CONSTRUCTION BY THE DESIGN ENGINEER AND THE CITY ENGINEERING DIVISION.

3. IF THE EROSION CONTROL PLAN AS APPROVED CANNOT CONTROL EROSION AND OFF-SITE SEDIMENTATION FROM THE PROJECT, THE EROSION CONTROL PLAN WILL BE REQUIRED TO BE REVISED AND/OR ADDITIONAL EROSION CONTROL DEVICES WILL BE REQUIRED ON SITE.

4. INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO INSURE THAT THE DEVICES ARE FUNCTIONING PROPERLY. WHEN SEDIMENT OR MUD HAS CLOGGED THE VOID SPACES BETWEEN STONES OR MUD IS BEING TRACKED ONTO A PUBLIC ROADWAY THE AGGREGATE PAD MUST BE WASHED DOWN OR REPLACED. RUNOFF FROM THE WASHDOWN OPERATION SHALL NOT BE ALLOWED TO DRAIN DIRECTLY OFF SITE WITHOUT FIRST FLOWING THROUGH ANOTHER BMP TO CONTROL OFF SITE SEDIMENTATION. PERIODIC RE-GRADING OR THE ADDITION OF NEW STONE MAY BE REQUIRED TO MAINTAIN THE EFFICIENCY OF THE INSTALLATION.

5. CONTRACTOR SHALL BE RESPONSIBLE FOR SUBMITTAL OF N.O.I., N.O.T. AND ANY ADDITIONAL INFORMATION REQUIRED BY THE TCEQ IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS FOR THIS PROJECT. CHANGES ARE TO BE APPROVED BEFORE CONSTRUCTION BY THE DESIGN ENGINEER AND THE CITY ENGINEERING DIVISION.

BMP MAINTENANCE SCHEDULE

TEMPORARY STONE CONSTRUCTION ENTRANCE/EXIT:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. AGGREGATE PAD SHALL BE WASHED DOWN OR REPLACED WHEN SEDIMENT OR MUD HAS CLOGGED THE VOID SPACES BETWEEN THE STONES OR MUD IS BEING TRACKED ONTO THE PUBLIC ROADWAY. RUNOFF FROM WASHDOWN OPERATION SHALL BE FILTERED THROUGH ANOTHER B.M.P. PRIOR TO DRAINING OFF-SITE.

SILT FENCE:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. SEDIMENT SHALL BE REMOVED FROM THE STORAGE AREA WHEN SEDIMENT DEPTH HAS BUILT UP TO ONE-HALF THE HEIGHT OF THE STONE OUTLET. REPAIR DISLODGED OR MISSING STONE RIP-RAP AND REPAIR ANY DOWNSTREAM EROSION.

STONE OVERFLOW STRUCTURE:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. SEDIMENT SHALL BE REMOVED FROM THE STORAGE AREA WHEN SEDIMENT DEPTH HAS BUILT UP TO ONE-HALF THE HEIGHT OF THE STONE OUTLET. REPAIR DISLODGED OR MISSING STONE RIP-RAP AND REPAIR ANY DOWNSTREAM EROSION.

ROCK CHECK DAM:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA UPSTREAM OF THE DAM WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE DAM HEIGHT. REPAIR DAMAGE TO THE CHANNEL IN THE VICINITY OF THE CHECK DAMS IMMEDIATELY TO PREVENT ADDITIONAL DAMAGE. REPLACE MISSING OR DISLODGED ROCK AS NEEDED TO MAINTAIN THE DESIGN HEIGHT AND CROSS SECTION OF THE CHECK DAM.

CURB INLET/GRATE INLET/WYVE INLET:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA SURROUNDING THE INLET/GRATE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE PROTECTION HEIGHT. DEVICE SHALL BE INSPECTED FOR GAPS AT BASE, AND SHALL BE REPLACED AS NEEDED.

VEGETATIVE STABILIZATION REQUIREMENTS

TEMPORARY SEEDING

ALL DISTURBED AREAS WHICH WILL BE LEFT DORMANT FOR GREATER THAN 14 DAYS SHALL BE SEED WITH FAST-GERMINATING TEMPORARY VEGETATION IMMEDIATELY FOLLOWING GRADING OPERATIONS. SELECTION OF THE SEED WILL DEPEND ON THE TIME OF YEAR IT IS APPLIED (SEE DESCRIPTIONS IN TABLE 2). REFERENCE LANDSCAPE PLAN FOR PERMANENT STABILIZATION REQUIREMENTS. ALL TEMPORARY SEEDING MATERIALS SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE PRIOR TO APPLICATION.

TABLE 2
VEGETATION TABLE*

TEMPORARY SEEDING SPECIES	PLANTING RATE	PLANTING DATES
CRIMSON CLOVER	7#/ACRE	8/15 - 11/30
MILLET, FOXTAIL	30#/ACRE	9/1 - 9/31
RYEGRASS, ANNUAL	30#/ACRE	8/15 - 9/30
SPRANGLETOP, GREEN	25#/ACRE	2/1 - 5/1
TALL FESCUE	7#-10#/1000 SF	9/1 - 10/15

*USE ONLY USDA CERTIFIED SEED.

SURFACE PREPARATION FOR TEMPORARY SEEDING

1. INSTALL EROSION STRUCTURES SUCH AS DIKES, DIVERSIONS, ETC. PRIOR TO SEEDING.

2. FURROW SLOPES STEEPER THAN 3:1 ON THE CONTOUR LINE BEFORE SEEDING.

3. ENSURE SEED BED IS PULVERIZED, LOOSE, AND UNIFORM.

APPLICATION

1. WHEN HYDROMULCHING IS USED, DO NOT MIX SEED AND FERTILIZER MORE THAN 30 MINUTES PRIOR TO APPLICATION.

2. APPLY SEED EVENLY USING PROPER EQUIPMENT AND WATER TO AID VEGETATION GROWTH.

3. EROSION CONTROL NETTING SHALL BE INSTALLED OVER FILL SLOPES WHICH HAVE BEEN BROUGHT TO FINAL GRADE AND HAVE BEEN SEED TO PROTECT AGAINST EROSION. MULCH (STRAW OR FIBER) SHALL BE USED ON RELATIVELY FLAT SLOPES.

Kimley»Horn

© 2025 KIMLEY-HORN AND ASSOCIATES, INC.
6180 WARREN PARKWAY, SUITE 210, FRISCO, TX 75034
PHONE: 972-335-3580
WWW.KIMLEY-HORN.COM
TEXAS REGISTERED ENGINEERING FIRM F-928

STATE OF TEXAS
JOHN HALE
145933
LICENSED PROFESSIONAL ENGINEER
6/6/17/2025

SCALE
AS SHOWN
DESIGNED BY
JNC
DRAWN BY
JNC
CHECKED BY
JTH

EROSION CONTROL PLAN

BAKER TRACT
OFFSITE SEWER
CITY OF DENTON, TEXAS

DATE
06/11/25

PROJECT NO.
063248015




SHEET NUMBER
C17.06

REVISIONS

No.

DATE

Plotted By: Browning, Moson Date: June 11, 2025 08:41:34am File Path: K:\Vr1_civil\063248015 - baker tract offsite sewer\CAD\plansheets\C-Eros.dwg
This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



LEGEND

	PROPERTY LINE		SILT FENCE
	PROPOSED CONTOUR		LIMITS OF DISTURBANCE
	EXISTING CONTOUR		INLET PROTECTION

EROSION CONTROL SCHEDULE AND PHASING

- THE PROJECT SHALL GENERALLY CONFORM TO THE FOLLOWING:
- PHASE A - GRADING**
1. CONSTRUCT TEMPORARY CONSTRUCTION ENTRANCE, SILT FENCE, DIKE, AND TREE PROTECTION FENCE ACCORDING TO THE APPROXIMATE LOCATION AND SHOWN ON EROSION CONTROL PLAN NOTES AND DETAIL SHEET.
 2. BEGIN CLEARING AND GRADING OF SITE.
 3. SEED AND REVEGETATE SLOPES WHERE SHOWN.
- PHASE B - UTILITIES**
1. KEEP ALL STORM WATER POLLUTION PREVENTION MEASURES IN PLACE.
 2. INSTALL STORM DRAINS, SANITARY SEWER, AND WATER AS SPECIFIED ON PLAN SHEETS.
- PHASE C - LANDSCAPING AND SOIL STABILIZATION**
1. REVEGETATE LOT AND PARKWAYS
 2. LANDSCAPE CONTRACTOR SHALL REVEGETATE ALL AREAS RESERVED FOR LANDSCAPE VEGETATIVE COVERS.
 3. REMOVE EROSION CONTROL DEVICES WHEN MINIMUM 70% GROUND COVER IS ESTABLISHED.
- VEGETATION MUST BE ESTABLISHED BEFORE STRUCTURAL CONTROLS REMOVED.

SITE MAP GENERAL NOTES

1. CONTRACTOR IS SOLELY RESPONSIBLE FOR SELECTION, IMPLEMENTATION, MAINTENANCE, AND EFFECTIVENESS OF ALL SWPPP CONTROLS - CONTROLS SHOWN ON THIS SITE MAP ARE SUGGESTED CONTROLS ONLY.
2. CONTRACTOR SHALL RECORD INSTALLATION, MAINTENANCE OR MODIFICATION, AND REMOVAL DATES FOR EACH BMP EMPLOYED (WHETHER CALLED OUT ON ORIGINAL SWPPP OR NOT) DIRECTLY ON THE SITE MAP.
3. TEMPORARY AND PERMANENT STABILIZATION PRACTICES AND BMP'S SHALL BE INSTALLED AT THE EARLIEST POSSIBLE TIME DURING THE CONSTRUCTION SEQUENCE. AS AN EXAMPLE, PERIMETER SILT FENCE SHALL BE INSTALLED BEFORE COMMENCEMENT OF ANY GRADING ACTIVITIES. OTHER BMP'S SHALL BE INSTALLED AS SOON AS PRACTICABLE AND SHALL BE MAINTAINED UNTIL FINAL SITE STABILIZATION IS ATTAINED. CONTRACTOR SHALL ALSO REFERENCE CIVIL AND LANDSCAPE PLANS SINCE PERMANENT STABILIZATION IS PROVIDED BY LANDSCAPING, THE BUILDING(S), AND SITE PAVING.
4. BMP'S HAVE BEEN LOCATED AS INDICATED ON THIS PLAN IN ACCORDANCE WITH GENERALLY ACCEPTED ENGINEERING PRACTICES IN ORDER TO MINIMIZE SEDIMENT TRANSFER. FOR EXAMPLE, SILT FENCES LOCATED AT TOE OF SLOPE AND INLET PROTECTION FOR INLETS RECEIVING SEDIMENT FROM SITE RUN-OFF.
5. SANITARY SEWER EFFLUENT IS DISPOSED OF VIA AN ONSITE SEWER SYSTEM CONNECTED TO A MUNICIPAL SEWER SYSTEM.

STANDARD EROSION CONTROL GENERAL NOTES

1. EROSION CONTROL DEVICES SHOWN ON THIS PLAN SHALL BE INSTALLED PRIOR TO THE START OF LAND DISTURBING ACTIVITIES ON THE PROJECT.
2. ALL EROSION CONTROL DEVICES ARE TO BE INSTALLED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS FOR THIS PROJECT. CHANGES ARE TO BE APPROVED BEFORE CONSTRUCTION BY THE DESIGN ENGINEER AND THE CITY ENGINEERING DIVISION.
3. IF THE EROSION CONTROL PLAN AS APPROVED CANNOT CONTROL EROSION AND OFF-SITE SEDIMENTATION FROM THE PROJECT, THE EROSION CONTROL PLAN WILL BE REQUIRED TO BE REVISED AND/OR ADDITIONAL EROSION CONTROL DEVICES WILL BE REQUIRED ON SITE.
4. INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO INSURE THAT THE DEVICES ARE FUNCTIONING PROPERLY. WHEN SEDIMENT OR MUD HAS CLOGGED THE VOID SPACES BETWEEN STONES OR MUD IS BEING TRACKED ONTO A PUBLIC ROADWAY THE AGGREGATE PAD MUST BE WASHED DOWN OR REPLACED. RUNOFF FROM THE WASHDOWN OPERATION SHALL NOT BE ALLOWED TO DRAIN DIRECTLY OFF SITE WITHOUT FIRST FLOWING THROUGH ANOTHER BMP TO CONTROL OFF SITE SEDIMENTATION. PERIODIC RE-GRADING OR THE ADDITION OF NEW STONE MAY BE REQUIRED TO MAINTAIN THE EFFICIENCY OF THE INSTALLATION.
5. CONTRACTOR SHALL BE RESPONSIBLE FOR SUBMITTAL OF N.O.I., N.O.T. AND ANY ADDITIONAL INFORMATION REQUIRED BY THE TCEQ IN ACCORDANCE WITH THE TCEQ STORMWATER POLLUTION PREVENTION REQUIREMENTS.

BMP MAINTENANCE SCHEDULE

TEMPORARY STONE CONSTRUCTION ENTRANCE/EXIT:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. AGGREGATE PAD SHALL BE WASHED DOWN OR REPLACED WHEN SEDIMENT OR MUD HAS CLOGGED THE VOID SPACES BETWEEN THE STONES OR MUD IS BEING TRACKED ONTO THE PUBLIC ROADWAY. RUNOFF FROM WASHDOWN OPERATION SHALL BE FILTERED THROUGH ANOTHER B.M.P. PRIOR TO DRAINING OFF-SITE.

SILT FENCE:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. SEDIMENT SHALL BE REMOVED FROM THE STORAGE AREA WHEN SEDIMENT DEPTH HAS BUILT UP TO ONE-HALF THE HEIGHT OF THE DAM HEIGHT. REPAIR DISLODGED OR MISSING STONE RIP-RAP AND REPAIR ANY DOWNSTREAM EROSION.

STONE OVERFLOW STRUCTURE:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. SEDIMENT SHALL BE REMOVED FROM THE STORAGE AREA UPSTREAM OF THE DAM WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE DAM HEIGHT. REPAIR DAMAGE TO THE CHANNEL IN THE VICINITY OF THE CHECK DAMS IMMEDIATELY TO PREVENT ADDITIONAL DAMAGE. REPLACE MISSING OR DISLODGED ROCK AS NEEDED TO MAINTAIN THE DESIGN HEIGHT AND CROSS SECTION OF THE CHECK DAM.

ROCK CHECK DAM:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA SURROUNDING THE INLET/GRATE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE PROTECTION HEIGHT. DEVICE SHALL BE INSPECTED FOR GAPS AT BASE, AND SHALL BE REPLACED AS NEEDED.

CURB INLET/GRATE INLET/WYVE INLET:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA SURROUNDING THE INLET/GRATE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE PROTECTION HEIGHT. DEVICE SHALL BE INSPECTED FOR GAPS AT BASE, AND SHALL BE REPLACED AS NEEDED.

VEGETATIVE STABILIZATION REQUIREMENTS

TEMPORARY SEEDING

ALL DISTURBED AREAS WHICH WILL BE LEFT DORMANT FOR GREATER THAN 14 DAYS SHALL BE SEEDED WITH FAST-GERMINATING TEMPORARY VEGETATION IMMEDIATELY FOLLOWING GRADING OPERATIONS. SELECTION OF THE SEED WILL DEPEND ON THE TIME OF YEAR IT IS APPLIED (SEE DESCRIPTIONS IN TABLE 2). REFERENCE LANDSCAPE PLAN FOR PERMANENT STABILIZATION REQUIREMENTS. ALL TEMPORARY SEEDING MATERIALS SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE PRIOR TO APPLICATION.

TABLE 2
VEGETATION TABLE*

TEMPORARY SEEDING SPECIES	PLANTING RATE	PLANTING DATES
CRIMSON CLOVER	7#/ACRE	8/15 - 11/30
MILLET, FOXTAIL	30#/ACRE	9/1 - 9/31
RYEGRASS, ANNUAL	30#/ACRE	8/15 - 9/30
SPRANGLETOP, GREEN	25#/ACRE	2/1 - 5/1
TALL FESCUE	7#-10#/1000 SF	9/1 - 10/15

*USE ONLY USDA CERTIFIED SEED.

SURFACE PREPARATION FOR TEMPORARY SEEDING

1. INSTALL EROSION STRUCTURES SUCH AS DIKES, DIVERSIONS, ETC. PRIOR TO SEEDING.

2. FURROW SLOPES STEEPER THAN 3:1 ON THE CONTOUR LINE BEFORE SEEDING.

3. ENSURE SEED BED IS PULVERIZED, LOOSE, AND UNIFORM.

APPLICATION




1. WHEN HYDROMULCHING IS USED, DO NOT MIX SEED AND FERTILIZER MORE THAN 30 MINUTES PRIOR TO APPLICATION.

2. APPLY SEED EVENLY USING PROPER EQUIPMENT AND WATER TO AID VEGETATION GROWTH.

3. EROSION CONTROL NETTING SHALL BE INSTALLED OVER FILL SLOPES WHICH HAVE BEEN BROUGHT TO FINAL GRADE AND HAVE BEEN SEEDED TO PROTECT AGAINST EROSION. MULCH (STRAW OR FIBER) SHALL BE USED ON RELATIVELY FLAT SLOPES.

Plotted By: Browning, Moson Date: June 11, 2025 08:41:44am File Path: K:\VrL_civil\063248015 - baker tract offsite sewer\CAD\plansheets\C-Eros.dwg

This document, together with the concepts and designs presented herein, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



LEGEND

---	PROPERTY LINE
---	PROPOSED CONTOUR
---	EXISTING CONTOUR
---	SF
---	LD
---	IP
---	SILT FENCE
---	LIMITS OF DISTURBANCE
---	INLET PROTECTION

EROSION CONTROL SCHEDULE AND PHASING

- THE PROJECT SHALL GENERALLY CONFORM TO THE FOLLOWING:
- PHASE A - GRADING**
1. CONSTRUCT TEMPORARY CONSTRUCTION ENTRANCE, SILT FENCE, DIKE, AND TREE PROTECTION FENCE ACCORDING TO THE APPROXIMATE LOCATION AND SHOWN ON EROSION CONTROL PLAN NOTES AND DETAIL SHEET.
 2. BEGIN CLEARING AND GRADING OF SITE.
 3. SEED AND REVEGETATE SLOPES WHERE SHOWN.
- PHASE B - UTILITIES**
1. KEEP ALL STORM WATER POLLUTION PREVENTION MEASURES IN PLACE.
 2. INSTALL STORM DRAINS, SANITARY SEWER, AND WATER AS SPECIFIED ON PLAN SHEETS.
- PHASE C - LANDSCAPING AND SOIL STABILIZATION.**
1. REVEGETATE LOT AND PARKWAYS
 2. LANDSCAPE CONTRACTOR SHALL REVEGETATE ALL AREAS RESERVED FOR LANDSCAPE VEGETATIVE COVERS.
 3. REMOVE EROSION CONTROL DEVICES WHEN MINIMUM 70% GROUND COVER IS ESTABLISHED.
- VEGETATION MUST BE ESTABLISHED BEFORE STRUCTURAL CONTROLS REMOVED.

SITE MAP GENERAL NOTES

1. CONTRACTOR IS SOLELY RESPONSIBLE FOR SELECTION, IMPLEMENTATION, MAINTENANCE, AND EFFECTIVENESS OF ALL SWPPP CONTROLS - CONTROLS SHOWN ON THIS SITE MAP ARE SUGGESTED CONTROLS ONLY.
2. CONTRACTOR SHALL RECORD INSTALLATION, MAINTENANCE OR MODIFICATION, AND REMOVAL DATES FOR EACH BMP EMPLOYED (WHETHER CALLED OUT ON ORIGINAL SWPPP OR NOT) DIRECTLY ON THE SITE MAP.
3. TEMPORARY AND PERMANENT STABILIZATION PRACTICES AND BMP'S SHALL BE INSTALLED AT THE EARLIEST POSSIBLE TIME DURING THE CONSTRUCTION SEQUENCE. AS AN EXAMPLE, PERIMETER SILT FENCE SHALL BE INSTALLED BEFORE COMMENCEMENT OF ANY GRADING ACTIVITIES. OTHER BMP'S SHALL BE INSTALLED AS SOON AS PRACTICABLE AND SHALL BE MAINTAINED UNTIL FINAL SITE STABILIZATION IS ATTAINED. CONTRACTOR SHALL ALSO REFERENCE CIVIL AND LANDSCAPE PLANS SINCE PERMANENT STABILIZATION IS PROVIDED BY LANDSCAPING, THE BUILDING(S), AND SITE PAVING.
4. BMP'S HAVE BEEN LOCATED AS INDICATED ON THIS PLAN IN ACCORDANCE WITH GENERALLY ACCEPTED ENGINEERING PRACTICES IN ORDER TO MINIMIZE SEDIMENT TRANSFER. FOR EXAMPLE, SILT FENCES LOCATED AT TOE OF SLOPE AND INLET PROTECTION FOR INLETS RECEIVING SEDIMENT FROM SITE RUN-OFF.
5. SANITARY SEWER EFFLUENT IS DISPOSED OF VIA AN ONSITE SEWER SYSTEM CONNECTED TO A MUNICIPAL SEWER SYSTEM.

STANDARD EROSION CONTROL GENERAL NOTES

1. EROSION CONTROL DEVICES SHOWN ON THIS PLAN SHALL BE INSTALLED PRIOR TO THE START OF LAND DISTURBING ACTIVITIES ON THE PROJECT.
2. ALL EROSION CONTROL DEVICES ARE TO BE INSTALLED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS FOR THIS PROJECT. CHANGES ARE TO BE APPROVED BEFORE CONSTRUCTION BY THE DESIGN ENGINEER AND THE CITY ENGINEERING DIVISION.
3. IF THE EROSION CONTROL PLAN AS APPROVED CANNOT CONTROL EROSION AND OFF-SITE SEDIMENTATION FROM THE PROJECT, THE EROSION CONTROL PLAN WILL BE REQUIRED TO BE REVISED AND/OR ADDITIONAL EROSION CONTROL DEVICES WILL BE REQUIRED ON SITE.
4. INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO INSURE THAT THE DEVICES ARE FUNCTIONING PROPERLY. WHEN SEDIMENT OR MUD HAS CLOGGED THE VOID SPACES BETWEEN STONES OR MUD IS BEING TRACKED ONTO A PUBLIC ROADWAY THE AGGREGATE PAD MUST BE WASHED DOWN OR REPLACED. RUNOFF FROM THE WASHDOWN OPERATION SHALL NOT BE ALLOWED TO DRAIN DIRECTLY OFF SITE WITHOUT FIRST FLOWING THROUGH ANOTHER BMP TO CONTROL OFF SITE SEDIMENTATION. PERIODIC RE-GRADING OR THE ADDITION OF NEW STONE MAY BE REQUIRED TO MAINTAIN THE EFFICIENCY OF THE INSTALLATION.
5. CONTRACTOR SHALL BE RESPONSIBLE FOR SUBMITTAL OF N.O.I., N.O.T. AND ANY ADDITIONAL INFORMATION REQUIRED BY THE TCEQ.

BMP MAINTENANCE SCHEDULE

TEMPORARY STONE CONSTRUCTION ENTRANCE/EXIT:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. AGGREGATE PAD SHALL BE WASHED DOWN OR REPLACED WHEN SEDIMENT OR MUD HAS CLOGGED THE VOID SPACES BETWEEN THE STONES OR MUD IS BEING TRACKED ONTO THE PUBLIC ROADWAY. RUNOFF FROM WASHDOWN OPERATION SHALL BE FILTERED THROUGH ANOTHER B.M.P. PRIOR TO DRAINING OFF-SITE.

SILT FENCE:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS. SEDIMENT SHALL BE REMOVED FROM BEHIND THE FENCE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF THE HEIGHT OF THE FENCE ABOVE GRADE. FENCE SHALL BE INSPECTED FOR GAPS AT BASE. INSPECT SUPPORTING POSTS AND FILTER FABRIC. REPLACE IF REQUIRED.

STONE OVERFLOW STRUCTURE:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. SEDIMENT SHALL BE REMOVED FROM THE STORAGE AREA WHEN SEDIMENT DEPTH HAS BUILT UP TO ONE-HALF THE HEIGHT OF THE STONE OUTLET. REPAIR DISLODGED OR MISSING STONE RIP-RAP AND REPAIR ANY DOWNSTREAM EROSION.

ROCK CHECK DAM:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA UPSTREAM OF THE DAM WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE DAM HEIGHT. REPAIR DAMAGE TO THE CHANNEL IN THE VICINITY OF THE CHECK DAMS IMMEDIATELY TO PREVENT ADDITIONAL DAMAGE. REPLACE MISSING OR DISLODGED ROCK AS NEEDED TO MAINTAIN THE DESIGN HEIGHT AND CROSS SECTION OF THE CHECK DAM.

CURB INLET/GRATE INLET/WYVE INLET:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA SURROUNDING THE INLET/GRATE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE PROTECTION HEIGHT. DEVICE SHALL BE INSPECTED FOR GAPS AT BASE, AND SHALL BE REPLACED AS NEEDED.

VEGETATIVE STABILIZATION REQUIREMENTS

TEMPORARY SEEDING

ALL DISTURBED AREAS WHICH WILL BE LEFT DORMANT FOR GREATER THAN 14 DAYS SHALL BE SEEDED WITH FAST-GERMINATING TEMPORARY VEGETATION IMMEDIATELY FOLLOWING GRADING OPERATIONS. SELECTION OF THE SEED WILL DEPEND ON THE TIME OF YEAR IT IS APPLIED (SEE DESCRIPTIONS IN TABLE 2). REFERENCE LANDSCAPE PLAN FOR PERMANENT STABILIZATION REQUIREMENTS. ALL TEMPORARY SEEDING MATERIALS SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE PRIOR TO APPLICATION.

TABLE 2

SPECIES	PLANTING RATE	PLANTING DATES
CRIMSON CLOVER	7#/ACRE	8/15 - 11/30
MILLET, FOXTAIL	30#/ACRE	9/1 - 9/31
RYEGRASS, ANNUAL	30#/ACRE	8/15 - 9/30
SPRANGLETOP, GREEN	25#/ACRE	2/1 - 5/1
TALL FESCUE	7#-10#/1000 SF	9/1 - 10/15

*USE ONLY USDA CERTIFIED SEED.

SURFACE PREPARATION FOR TEMPORARY SEEDING

1. INSTALL EROSION STRUCTURES SUCH AS DIKES, DIVERSIONS, ETC. PRIOR TO SEEDING.

2. FURROW SLOPES STEEPER THAN 3:1 ON THE CONTOUR LINE BEFORE SEEDING.


3. ENSURE SEED BED IS PULVERIZED, LOOSE, AND UNIFORM.

APPLICATION

1. WHEN HYDROMULCHING IS USED, DO NOT MIX SEED AND FERTILIZER MORE THAN 30 MINUTES PRIOR TO APPLICATION.

2. APPLY SEED EVENLY USING PROPER EQUIPMENT AND WATER TO AID VEGETATION GROWTH.

3. EROSION CONTROL NETTING SHALL BE INSTALLED OVER FILL SLOPES WHICH HAVE BEEN BROUGHT TO FINAL GRADE AND HAVE BEEN SEEDED TO PROTECT AGAINST EROSION. MULCH (STRAW OR FIBER) SHALL BE USED ON RELATIVELY FLAT SLOPES.



CONTRACTOR TO RESTORE GRADE TO EXISTING
CONDITIONS AFTER INSTALLATION OF SEWER LINE

EROSION CONTROL SCHEDULE AND PHASING

THE PROJECT SHALL GENERALLY CONFORM TO THE FOLLOWING:

- PHASE A - GRADING**
1. CONSTRUCT TEMPORARY CONSTRUCTION ENTRANCE, SILT FENCE, DIKE, AND TREE PROTECTION FENCE ACCORDING TO THE APPROXIMATE LOCATION AND SHOWN ON EROSION CONTROL PLAN NOTES AND DETAIL SHEET.
 2. BEGIN CLEARING AND GRADING OF SITE.
 3. SEED AND REVEGETATE SLOPES WHERE SHOWN.
- PHASE B - UTILITIES**
1. KEEP ALL STORM WATER POLLUTION PREVENTION MEASURES IN PLACE.
 2. INSTALL STORM DRAINS, SANITARY SEWER, AND WATER AS SPECIFIED ON PLAN SHEETS.
- PHASE C - LANDSCAPING AND SOIL STABILIZATION.**
1. REVEGETATE LOT AND PARKWAYS
 2. LANDSCAPE CONTRACTOR SHALL REVEGETATE ALL AREAS RESERVED FOR LANDSCAPE VEGETATIVE COVERS.
 3. REMOVE EROSION CONTROL DEVICES WHEN MINIMUM 70% GROUND COVER IS ESTABLISHED.
- VEGETATION MUST BE ESTABLISHED BEFORE STRUCTURAL CONTROLS REMOVED.

SITE MAP GENERAL NOTES

1. CONTRACTOR IS SOLELY RESPONSIBLE FOR SELECTION, IMPLEMENTATION, MAINTENANCE, AND EFFECTIVENESS OF ALL SWPPP CONTROLS - CONTROLS SHOWN ON THIS SITE MAP ARE SUGGESTED CONTROLS ONLY.
2. CONTRACTOR SHALL RECORD INSTALLATION, MAINTENANCE OR MODIFICATION, AND REMOVAL DATES FOR EACH BMP EMPLOYED (WHETHER CALLED OUT ON ORIGINAL SWPPP OR NOT) DIRECTLY ON THE SITE MAP.
3. TEMPORARY AND PERMANENT STABILIZATION PRACTICES AND BMP'S SHALL BE INSTALLED AT THE EARLIEST POSSIBLE TIME DURING THE CONSTRUCTION SEQUENCE. AS AN EXAMPLE, PERIMETER SILT FENCE SHALL BE INSTALLED BEFORE COMMENCEMENT OF ANY GRADING ACTIVITIES. OTHER BMP'S SHALL BE INSTALLED AS SOON AS PRACTICABLE AND SHALL BE MAINTAINED UNTIL FINAL SITE STABILIZATION IS ATTAINED. CONTRACTOR SHALL ALSO REFERENCE CIVIL AND LANDSCAPE PLANS SINCE PERMANENT STABILIZATION IS PROVIDED BY LANDSCAPING, THE BUILDING(S), AND SITE PAVING.
4. BMP'S HAVE BEEN LOCATED AS INDICATED ON THIS PLAN IN ACCORDANCE WITH GENERALLY ACCEPTED ENGINEERING PRACTICES IN ORDER TO MINIMIZE SEDIMENT TRANSFER. FOR EXAMPLE, SILT FENCES LOCATED AT TOE OF SLOPE AND INLET PROTECTION FOR INLETS RECEIVING SEDIMENT FROM SITE RUN-OFF.
5. SANITARY SEWER EFFLUENT IS DISPOSED OF VIA AN ONSITE SEWER SYSTEM CONNECTED TO A MUNICIPAL SEWER SYSTEM.

STANDARD EROSION CONTROL GENERAL NOTES

1. EROSION CONTROL DEVICES SHOWN ON THIS PLAN SHALL BE INSTALLED PRIOR TO THE START OF LAND DISTURBING ACTIVITIES ON THE PROJECT.
2. ALL EROSION CONTROL DEVICES ARE TO BE INSTALLED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS FOR THIS PROJECT. CHANGES ARE TO BE APPROVED BEFORE CONSTRUCTION BY THE DESIGN ENGINEER AND THE CITY ENGINEERING DIVISION.
3. IF THE EROSION CONTROL PLAN AS APPROVED CANNOT CONTROL EROSION AND OFF-SITE SEDIMENTATION FROM THE PROJECT, THE EROSION CONTROL PLAN WILL BE REQUIRED TO BE REVISED AND/OR ADDITIONAL EROSION CONTROL DEVICES WILL BE REQUIRED ON SITE.
4. INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO INSURE THAT THE DEVICES ARE FUNCTIONING PROPERLY. WHEN SEDIMENT OR MUD HAS CLOGGED THE VOID SPACES BETWEEN STONES OR MUD IS BEING TRACKED ONTO A PUBLIC ROADWAY THE AGGREGATE PAD MUST BE WASHED DOWN OR REPLACED. RUNOFF FROM THE WASHDOWN OPERATION SHALL NOT BE ALLOWED TO DRAIN DIRECTLY OFF SITE WITHOUT FIRST FLOWING THROUGH ANOTHER BMP TO CONTROL OFF SITE SEDIMENTATION. PERIODIC RE-GRADING OR THE ADDITION OF NEW STONE MAY BE REQUIRED TO MAINTAIN THE EFFICIENCY OF THE INSTALLATION.
5. CONTRACTOR SHALL BE RESPONSIBLE FOR SUBMITTAL OF N.O.I., N.O.T. AND ANY ADDITIONAL INFORMATION REQUIRED BY THE TCEQ IN ACCORDANCE WITH THE TCEQ STORMWATER POLLUTION PREVENTION REQUIREMENTS.

BMP MAINTENANCE SCHEDULE

TEMPORARY STONE CONSTRUCTION ENTRANCE/EXIT:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. AGGREGATE PAD SHALL BE WASHED DOWN OR REPLACED WHEN SEDIMENT OR MUD HAS CLOGGED THE VOID SPACES BETWEEN THE STONES OR MUD IS BEING TRACKED ONTO THE PUBLIC ROADWAY. RUNOFF FROM WASHDOWN OPERATION SHALL BE FILTERED THROUGH ANOTHER B.M.P. PRIOR TO DRAINING OFF-SITE.

SILT FENCE:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS. SEDIMENT SHALL BE REMOVED FROM BEHIND THE FENCE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF THE HEIGHT OF THE FENCE ABOVE GRADE. FENCE SHALL BE INSPECTED FOR GAPS AT BASE. INSPECT SUPPORTING POSTS AND FILTER FABRIC. REPLACE IF REQUIRED.

STONE OVERFLOW STRUCTURE:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. SEDIMENT SHALL BE REMOVED FROM THE STORAGE AREA WHEN SEDIMENT DEPTH HAS BUILT UP TO ONE-HALF THE HEIGHT OF THE STONE OUTLET. REPAIR DISLODGED OR MISSING STONE RIP-RAP AND REPAIR ANY DOWNSTREAM EROSION.

ROCK CHECK DAM:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA UPSTREAM OF THE DAM WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE DAM HEIGHT. REPAIR DAMAGE TO THE CHANNEL IN THE VICINITY OF THE CHECK DAMS IMMEDIATELY TO PREVENT ADDITIONAL DAMAGE. REPLACE MISSING OR DISLODGED ROCK AS NEEDED TO MAINTAIN THE DESIGN HEIGHT AND CROSS SECTION OF THE CHECK DAM.

CURB INLET/GRATE INLET/WYVE INLET:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA SURROUNDING THE INLET/GRATE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE PROTECTION HEIGHT. DEVICE SHALL BE INSPECTED FOR GAPS AT BASE, AND SHALL BE REPLACED AS NEEDED.

VEGETATIVE STABILIZATION REQUIREMENTS

TEMPORARY SEEDING

ALL DISTURBED AREAS WHICH WILL BE LEFT DORMANT FOR GREATER THAN 14 DAYS SHALL BE SEED WITH FAST-GERMINATING TEMPORARY VEGETATION IMMEDIATELY FOLLOWING GRADING OPERATIONS. SELECTION OF THE SEED WILL DEPEND ON THE TIME OF YEAR IT IS APPLIED (SEE DESCRIPTIONS IN TABLE 2). REFERENCE LANDSCAPE PLAN FOR PERMANENT STABILIZATION REQUIREMENTS. ALL TEMPORARY SEEDING MATERIALS SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE PRIOR TO APPLICATION.

TABLE 2
VEGETATION TABLE*

TEMPORARY SEEDING SPECIES	PLANTING RATE	PLANTING DATES
CRIMSON CLOVER	7#/ACRE	8/15 - 11/30
MILLET, FOXTAIL	30#/ACRE	9/1 - 9/31
RYEGRASS, ANNUAL	30#/ACRE	8/15 - 9/30
SPRANGLETOP, GREEN	25#/ACRE	2/1 - 5/1
TALL FESCUE	7#-10#/1000 SF	9/1 - 10/15

*USE ONLY USDA CERTIFIED SEED.

SURFACE PREPARATION FOR TEMPORARY SEEDING

1. INSTALL EROSION STRUCTURES SUCH AS DIKES, DIVERSIONS, ETC. PRIOR TO SEEDING.

2. FURROW SLOPES STEEPER THAN 3:1 ON THE CONTOUR LINE BEFORE SEEDING.

3. ENSURE SEED BED IS PULVERIZED, LOOSE, AND UNIFORM.




APPLICATION

1. WHEN HYDROMULCHING IS USED, DO NOT MIX SEED AND FERTILIZER MORE THAN 30 MINUTES PRIOR TO APPLICATION.

2. APPLY SEED EVENLY USING PROPER EQUIPMENT AND WATER TO AID VEGETATION GROWTH.

3. EROSION CONTROL NETTING SHALL BE INSTALLED OVER FILL SLOPES WHICH HAVE BEEN BROUGHT TO FINAL GRADE AND HAVE BEEN SEEDING TO PROTECT AGAINST EROSION. MULCH (STRAW OR FIBER) SHALL BE USED ON RELATIVELY FLAT SLOPES.

Plotted By: Browning, Moson Date: June 11, 2025 08:42:04am File Path: K:\Jrnl_civil\063248015 - baker tract offsite sewer\CAD\plansheets\C-Eros.dwg
This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



LEGEND

---	PROPERTY LINE
---	PROPOSED CONTOUR
---	EXISTING CONTOUR
SF	SILT FENCE
LD	LIMITS OF DISTURBANCE
IP	INLET PROTECTION

EROSION CONTROL SCHEDULE AND PHASING

- THE PROJECT SHALL GENERALLY CONFORM TO THE FOLLOWING:
- PHASE A - GRADING**
1. CONSTRUCT TEMPORARY CONSTRUCTION ENTRANCE, SILT FENCE, DIKE, AND TREE PROTECTION FENCE ACCORDING TO THE APPROXIMATE LOCATION AND SHOWN ON EROSION CONTROL PLAN NOTES AND DETAIL SHEET.
 2. BEGIN CLEARING AND GRADING OF SITE.
 3. SEED AND REVEGETATE SLOPES WHERE SHOWN.
- PHASE B - UTILITIES**
1. KEEP ALL STORM WATER POLLUTION PREVENTION MEASURES IN PLACE.
 2. INSTALL STORM DRAINS, SANITARY SEWER, AND WATER AS SPECIFIED ON PLAN SHEETS.
- PHASE C - LANDSCAPING AND SOIL STABILIZATION.**
1. REVEGETATE LOT AND PARKWAYS
 2. LANDSCAPE CONTRACTOR SHALL REVEGETATE ALL AREAS RESERVED FOR LANDSCAPE VEGETATIVE COVERS.
 3. REMOVE EROSION CONTROL DEVICES WHEN MINIMUM 70% GROUND COVER IS ESTABLISHED.
- VEGETATION MUST BE ESTABLISHED BEFORE STRUCTURAL CONTROLS REMOVED.

SITE MAP GENERAL NOTES

1. CONTRACTOR IS SOLELY RESPONSIBLE FOR SELECTION, IMPLEMENTATION, MAINTENANCE, AND EFFECTIVENESS OF ALL SWPPP CONTROLS - CONTROLS SHOWN ON THIS SITE MAP ARE SUGGESTED CONTROLS ONLY.
2. CONTRACTOR SHALL RECORD INSTALLATION, MAINTENANCE OR MODIFICATION, AND REMOVAL DATES FOR EACH BMP EMPLOYED (WHETHER CALLED OUT ON ORIGINAL SWPPP OR NOT) DIRECTLY ON THE SITE MAP.
3. TEMPORARY AND PERMANENT STABILIZATION PRACTICES AND BMP'S SHALL BE INSTALLED AT THE EARLIEST POSSIBLE TIME DURING THE CONSTRUCTION SEQUENCE. AS AN EXAMPLE, PERIMETER SILT FENCE SHALL BE INSTALLED BEFORE COMMENCEMENT OF ANY GRADING ACTIVITIES. OTHER BMP'S SHALL BE INSTALLED AS SOON AS PRACTICABLE AND SHALL BE MAINTAINED UNTIL FINAL SITE STABILIZATION IS ATTAINED. CONTRACTOR SHALL ALSO REFERENCE CIVIL AND LANDSCAPE PLANS SINCE PERMANENT STABILIZATION IS PROVIDED BY LANDSCAPING, THE BUILDING(S), AND SITE PAVING.
4. BMP'S HAVE BEEN LOCATED AS INDICATED ON THIS PLAN IN ACCORDANCE WITH GENERALLY ACCEPTED ENGINEERING PRACTICES IN ORDER TO MINIMIZE SEDIMENT TRANSFER. FOR EXAMPLE, SILT FENCES LOCATED AT TOE OF SLOPE AND INLET PROTECTION FOR INLETS RECEIVING SEDIMENT FROM SITE RUN-OFF.
5. SANITARY SEWER EFFLUENT IS DISPOSED OF VIA AN ONSITE SEWER SYSTEM CONNECTED TO A MUNICIPAL SEWER SYSTEM.

BMP MAINTENANCE SCHEDULE

TEMPORARY STONE CONSTRUCTION ENTRANCE/EXIT:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. AGGREGATE PAD SHALL BE WASHED DOWN OR REPLACED WHEN SEDIMENT OR MUD HAS CLOGGED THE VOID SPACES BETWEEN THE STONES OR MUD IS BEING TRACKED ONTO THE PUBLIC ROADWAY. RUNOFF FROM WASHDOWN OPERATION SHALL BE FILTERED THROUGH ANOTHER B.M.P. PRIOR TO DRAINING OFF-SITE.

SILT FENCE:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS. SEDIMENT SHALL BE REMOVED FROM BEHIND THE FENCE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF THE HEIGHT OF THE FENCE ABOVE GRADE. FENCE SHALL BE INSPECTED FOR GAPS AT BASE. INSPECT SUPPORTING POSTS AND FILTER FABRIC. REPLACE IF REQUIRED.

STONE OVERFLOW STRUCTURE:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. SEDIMENT SHALL BE REMOVED FROM THE STORAGE AREA WHEN SEDIMENT DEPTH HAS BUILT UP TO ONE-HALF THE HEIGHT OF THE STONE OUTLET. REPAIR DISLODGED OR MISSING STONE RIP-RAP AND REPAIR ANY DOWNSTREAM EROSION.

ROCK CHECK DAM:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA UPSTREAM OF THE DAM WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE DAM HEIGHT. REPAIR DAMAGE TO THE CHANNEL IN THE VICINITY OF THE CHECK DAMS IMMEDIATELY TO PREVENT ADDITIONAL DAMAGE. REPLACE MISSING OR DISLODGED ROCK AS NEEDED TO MAINTAIN THE DESIGN HEIGHT AND CROSS SECTION OF THE CHECK DAM.

CURB INLET/GRATE INLET/WYVE INLET:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA SURROUNDING THE INLET/GRATE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE PROTECTION HEIGHT. DEVICE SHALL BE INSPECTED FOR GAPS AT BASE, AND SHALL BE REPLACED AS NEEDED.

STANDARD EROSION CONTROL GENERAL NOTES

1. EROSION CONTROL DEVICES SHOWN ON THIS PLAN SHALL BE INSTALLED PRIOR TO THE START OF LAND DISTURBING ACTIVITIES ON THE PROJECT.
2. ALL EROSION CONTROL DEVICES ARE TO BE INSTALLED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS FOR THIS PROJECT. CHANGES ARE TO BE APPROVED BEFORE CONSTRUCTION BY THE DESIGN ENGINEER AND THE CITY ENGINEERING DIVISION.
3. IF THE EROSION CONTROL PLAN AS APPROVED CANNOT CONTROL EROSION AND OFF-SITE SEDIMENTATION FROM THE PROJECT, THE EROSION CONTROL PLAN WILL BE REQUIRED TO BE REVISED AND/OR ADDITIONAL EROSION CONTROL DEVICES WILL BE REQUIRED ON SITE.
4. INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO INSURE THAT THE DEVICES ARE FUNCTIONING PROPERLY. WHEN SEDIMENT OR MUD HAS CLOGGED THE VOID SPACES BETWEEN STONES OR MUD IS BEING TRACKED ONTO A PUBLIC ROADWAY THE AGGREGATE PAD MUST BE WASHED DOWN OR REPLACED. RUNOFF FROM THE WASHDOWN OPERATION SHALL NOT BE ALLOWED TO DRAIN DIRECTLY OFF SITE WITHOUT FIRST FLOWING THROUGH ANOTHER BMP TO CONTROL OFF SITE SEDIMENTATION. PERIODIC RE-GRADING OR THE ADDITION OF NEW STONE MAY BE REQUIRED TO MAINTAIN THE EFFICIENCY OF THE INSTALLATION.
5. CONTRACTOR SHALL BE RESPONSIBLE FOR SUBMITTAL OF N.O.I., N.O.T. AND ANY ADDITIONAL INFORMATION REQUIRED BY THE TCEQ. CONTRACTOR SHALL COMPLY WITH ALL TCEQ STORMWATER POLLUTION PREVENTION REQUIREMENTS.

VEGETATIVE STABILIZATION REQUIREMENTS

TEMPORARY SEEDING

ALL DISTURBED AREAS WHICH WILL BE LEFT DORMANT FOR GREATER THAN 14 DAYS SHALL BE SEEDDED WITH FAST-GERMINATING TEMPORARY VEGETATION IMMEDIATELY FOLLOWING GRADING OPERATIONS. SELECTION OF THE SEED WILL DEPEND ON THE TIME OF YEAR IT IS APPLIED (SEE DESCRIPTIONS IN TABLE 2). REFERENCE LANDSCAPE PLAN FOR PERMANENT STABILIZATION REQUIREMENTS. ALL TEMPORARY SEEDING MATERIALS SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE PRIOR TO APPLICATION.

TABLE 2
VEGETATION TABLE*

TEMPORARY SEEDING SPECIES	PLANTING RATE	PLANTING DATES
CRIMSON CLOVER	7#/ACRE	8/15 - 11/30
MILLET, FOXTAIL	30#/ACRE	9/1 - 9/31
RYEGRASS, ANNUAL	30#/ACRE	8/15 - 9/30
SPRANGLETOP, GREEN	25#/ACRE	2/1 - 5/1
TALL FESCUE	7#-10#/1000 SF	9/1 - 10/15

*USE ONLY USDA CERTIFIED SEED.

SURFACE PREPARATION FOR TEMPORARY SEEDING

1. INSTALL EROSION STRUCTURES SUCH AS DIKES, DIVERSIONS, ETC. PRIOR TO SEEDING.

2. FURROW SLOPES STEEPER THAN 3:1 ON THE CONTOUR LINE BEFORE SEEDING.

3. ENSURE SEED BED IS PULVERIZED, LOOSE, AND UNIFORM.


APPLICATION

1. WHEN HYDROMULCHING IS USED, DO NOT MIX SEED AND FERTILIZER MORE THAN 30 MINUTES PRIOR TO APPLICATION.


2. APPLY SEED EVENLY USING PROPER EQUIPMENT AND WATER TO AID VEGETATION GROWTH.

3. EROSION CONTROL NETTING SHALL BE INSTALLED OVER FILL SLOPES WHICH HAVE BEEN BROUGHT TO FINAL GRADE AND HAVE BEEN SEEDDED TO PROTECT AGAINST EROSION. MULCH (STRAW OR FIBER) SHALL BE USED ON RELATIVELY FLAT SLOPES.


Plotted By: Browning, Moson Date: June 11, 2025 08:42:12am File Path: K:\VrL\civil\063248015 - baker tract offsite sewer\CAD\plansheets\C-Eros.dwg
This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



CONTRACTOR TO RESTORE GRADE TO EXISTING
CONDITIONS AFTER INSTALLATION OF SEWER LINE



GRAPHIC SCALE IN FEET



LEGEND

	PROPERTY LINE		SILT FENCE
	PROPOSED CONTOUR		LIMITS OF DISTURBANCE
	EXISTING CONTOUR		INLET PROTECTION

EROSION CONTROL SCHEDULE AND PHASING

- THE PROJECT SHALL GENERALLY CONFORM TO THE FOLLOWING:
- PHASE A - GRADING**
1. CONSTRUCT TEMPORARY CONSTRUCTION ENTRANCE, SILT FENCE, DIKE, AND TREE PROTECTION FENCE ACCORDING TO THE APPROXIMATE LOCATION AND SHOWN ON EROSION CONTROL PLAN NOTES AND DETAIL SHEET.
 2. BEGIN CLEARING AND GRADING OF SITE.
 3. SEED AND REVEGETATE SLOPES WHERE SHOWN.
- PHASE B - UTILITIES**
1. KEEP ALL STORM WATER POLLUTION PREVENTION MEASURES IN PLACE.
 2. INSTALL STORM DRAINS, SANITARY SEWER, AND WATER AS SPECIFIED ON PLAN SHEETS.
- PHASE C - LANDSCAPING AND SOIL STABILIZATION.**
1. REVEGETATE LOT AND PARKWAYS
 2. LANDSCAPE CONTRACTOR SHALL REVEGETATE ALL AREAS RESERVED FOR LANDSCAPE VEGETATIVE COVERS.
 3. REMOVE EROSION CONTROL DEVICES WHEN MINIMUM 70% GROUND COVER IS ESTABLISHED.
- VEGETATION MUST BE ESTABLISHED BEFORE STRUCTURAL CONTROLS REMOVED.

SITE MAP GENERAL NOTES

1. CONTRACTOR IS SOLELY RESPONSIBLE FOR SELECTION, IMPLEMENTATION, MAINTENANCE, AND EFFECTIVENESS OF ALL SWPPP CONTROLS - CONTROLS SHOWN ON THIS SITE MAP ARE SUGGESTED CONTROLS ONLY.
2. CONTRACTOR SHALL RECORD INSTALLATION, MAINTENANCE OR MODIFICATION, AND REMOVAL DATES FOR EACH BMP EMPLOYED (WHETHER CALLED OUT ON ORIGINAL SWPPP OR NOT) DIRECTLY ON THE SITE MAP.
3. TEMPORARY AND PERMANENT STABILIZATION PRACTICES AND BMP'S SHALL BE INSTALLED AT THE EARLIEST POSSIBLE TIME DURING THE CONSTRUCTION SEQUENCE. AS AN EXAMPLE, PERIMETER SILT FENCE SHALL BE INSTALLED BEFORE COMMENCEMENT OF ANY GRADING ACTIVITIES. OTHER BMP'S SHALL BE INSTALLED AS SOON AS PRACTICABLE AND SHALL BE MAINTAINED UNTIL FINAL SITE STABILIZATION IS ATTAINED. CONTRACTOR SHALL ALSO REFERENCE CIVIL AND LANDSCAPE PLANS SINCE PERMANENT STABILIZATION IS PROVIDED BY LANDSCAPING, THE BUILDING(S), AND SITE PAVING.
4. BMP'S HAVE BEEN LOCATED AS INDICATED ON THIS PLAN IN ACCORDANCE WITH GENERALLY ACCEPTED ENGINEERING PRACTICES IN ORDER TO MINIMIZE SEDIMENT TRANSFER. FOR EXAMPLE, SILT FENCES LOCATED AT TOE OF SLOPE AND INLET PROTECTION FOR INLETS RECEIVING SEDIMENT FROM SITE RUN-OFF.
5. SANITARY SEWER EFFLUENT IS DISPOSED OF VIA AN ONSITE SEWER SYSTEM CONNECTED TO A MUNICIPAL SEWER SYSTEM.

STANDARD EROSION CONTROL GENERAL NOTES

1. EROSION CONTROL DEVICES SHOWN ON THIS PLAN SHALL BE INSTALLED PRIOR TO THE START OF LAND DISTURBING ACTIVITIES ON THE PROJECT.
2. ALL EROSION CONTROL DEVICES ARE TO BE INSTALLED IN ACCORDANCE WITH THE APPROVED PLANS AND SPECIFICATIONS FOR THIS PROJECT. CHANGES ARE TO BE APPROVED BEFORE CONSTRUCTION BY THE DESIGN ENGINEER AND THE CITY ENGINEERING DIVISION.
3. IF THE EROSION CONTROL PLAN AS APPROVED CANNOT CONTROL EROSION AND OFF-SITE SEDIMENTATION FROM THE PROJECT, THE EROSION CONTROL PLAN WILL BE REQUIRED TO BE REVISED AND/OR ADDITIONAL EROSION CONTROL DEVICES WILL BE REQUIRED ON SITE.
4. INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO INSURE THAT THE DEVICES ARE FUNCTIONING PROPERLY. WHEN SEDIMENT OR MUD HAS CLOGGED THE VOID SPACES BETWEEN STONES OR MUD IS BEING TRACKED ONTO A PUBLIC ROADWAY THE AGGREGATE PAD MUST BE WASHED DOWN OR REPLACED. RUNOFF FROM THE WASHDOWN OPERATION SHALL NOT BE ALLOWED TO DRAIN DIRECTLY OFF SITE WITHOUT FIRST FLOWING THROUGH ANOTHER BMP TO CONTROL OFF SITE SEDIMENTATION. PERIODIC RE-GRADING OR THE ADDITION OF NEW STONE MAY BE REQUIRED TO MAINTAIN THE EFFICIENCY OF THE INSTALLATION.
5. CONTRACTOR SHALL BE RESPONSIBLE FOR SUBMITTAL OF N.O.I., N.O.T. AND ANY ADDITIONAL INFORMATION REQUIRED BY THE TCEQ.

BMP MAINTENANCE SCHEDULE

TEMPORARY STONE CONSTRUCTION ENTRANCE/EXIT:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. AGGREGATE PAD SHALL BE WASHED DOWN OR REPLACED WHEN SEDIMENT OR MUD HAS CLOGGED THE VOID SPACES BETWEEN THE STONES OR MUD IS BEING TRACKED ONTO THE PUBLIC ROADWAY. RUNOFF FROM WASHDOWN OPERATION SHALL BE FILTERED THROUGH ANOTHER B.M.P. PRIOR TO DRAINING OFF-SITE.

SILT FENCE:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS. SEDIMENT SHALL BE REMOVED FROM BEHIND THE FENCE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE DAM HEIGHT. THE FENCE ABOVE GRADE. FENCE SHALL BE INSPECTED FOR GAPS AT BASE. INSPECT SUPPORTING POSTS AND FILTER FABRIC. REPLACE IF REQUIRED.

STONE OVERFLOW STRUCTURE:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER RAIN STORM EVENTS TO ENSURE THAT THE FACILITY IS FUNCTIONING PROPERLY. SEDIMENT SHALL BE REMOVED FROM THE STORAGE AREA WHEN SEDIMENT DEPTH HAS BUILT UP TO ONE-HALF THE HEIGHT OF THE STONE OUTLET. REPAIR DISLODGED OR MISSING STONE RIP-RAP AND REPAIR ANY DOWNSTREAM EROSION.

ROCK CHECK DAM:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA UPSTREAM OF THE DAM WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE DAM HEIGHT. REPAIR DAMAGE TO THE CHANNEL IN THE VICINITY OF THE CHECK DAMS IMMEDIATELY TO PREVENT ADDITIONAL DAMAGE. REPLACE MISSING OR DISLODGED ROCK AS NEEDED TO MAINTAIN THE DESIGN HEIGHT AND CROSS SECTION OF THE CHECK DAM.

CURB INLET/GRATE INLET/WYE INLET:

INSPECTIONS SHALL BE MADE WEEKLY AND AFTER ALL RAIN EVENTS TO ENSURE THAT THE DEVICE IS FUNCTIONING PROPERLY. REMOVE SEDIMENT FROM THE STORAGE AREA SURROUNDING THE INLET/GRATE WHEN THE DEPTH OF SEDIMENT HAS BUILT UP TO ONE-HALF OF THE PROTECTION HEIGHT. DEVICE SHALL BE INSPECTED FOR GAPS AT BASE, AND SHALL BE REPLACED AS NEEDED.

VEGETATIVE STABILIZATION REQUIREMENTS

TEMPORARY SEEDING

ALL DISTURBED AREAS WHICH WILL BE LEFT DORMANT FOR GREATER THAN 14 DAYS SHALL BE SEEDDED WITH FAST-GERMINATING TEMPORARY VEGETATION IMMEDIATELY FOLLOWING GRADING OPERATIONS. SELECTION OF THE SEED WILL DEPEND ON THE TIME OF YEAR IT IS APPLIED (SEE DESCRIPTIONS IN TABLE 2). REFERENCE LANDSCAPE PLAN FOR PERMANENT STABILIZATION REQUIREMENTS. ALL TEMPORARY SEEDING MATERIALS SHALL BE APPROVED BY THE OWNER'S REPRESENTATIVE PRIOR TO APPLICATION.

TABLE 2
VEGETATION TABLE*

TEMPORARY SEEDING SPECIES	PLANTING RATE	PLANTING DATES
CRIMSON CLOVER	7#/ACRE	8/15 - 11/30
MILLET, FOXTAIL	30#/ACRE	8/1 - 9/31
RYEGRASS, ANNUAL	30#/ACRE	8/15 - 9/30
SPRANGLETOP, GREEN	25#/ACRE	2/1 - 5/1
TALL FESCUE	7#-10#/1000 SF	8/1 - 10/15

*USE ONLY USDA CERTIFIED SEED.

SURFACE PREPARATION FOR TEMPORARY SEEDING

1. INSTALL EROSION STRUCTURES SUCH AS DIKES, DIVERSIONS, ETC. PRIOR TO SEEDING.

2. FURROW SLOPES STEEPER THAN 3:1 ON THE CONTOUR LINE BEFORE SEEDING.

3. ENSURE SEED BED IS PULVERIZED, LOOSE, AND UNIFORM.

APPLICATION

1. WHEN HYDROMULCHING IS USED, DO NOT MIX SEED AND FERTILIZER MORE THAN 30 MINUTES PRIOR TO APPLICATION.

2. APPLY SEED EVENLY USING PROPER EQUIPMENT AND WATER TO AID VEGETATION GROWTH.

3. EROSION CONTROL NETTING SHALL BE INSTALLED OVER FILL SLOPES WHICH HAVE BEEN BROUGHT TO FINAL GRADE AND HAVE BEEN SEEDDED TO PROTECT AGAINST EROSION. MULCH (STRAW OR FIBER) SHALL BE USED ON RELATIVELY FLAT SLOPES.

REVISED IN 2018




FIGURE 3.29 STANDARD CONSTRUCTION DETAIL - STABILIZED CONSTRUCTION EXIT (1 OF 2)

STABILIZED CONSTRUCTION EXIT
REVISED

REVISED IN 2018




FIGURE 3.28 STANDARD CONSTRUCTION DETAIL - FOR SILT FENCE (1 OF 2)

SILT FENCE
REVISED

REVISED IN 2018




FIGURE 3.29 NOTES FOR STABILIZED CONSTRUCTION EXIT (2 OF 2)

STABILIZED CONSTRUCTION EXIT
REVISED

REVISED IN 2018






FIGURE 3.28 NOTES FOR SILT FENCE (2 OF 2)



SILT FENCE
REVISED

Plotted By: Browning, Mason Date: June 11, 2025 08:42:34am File Path: K:\Vri_civil\063248015 - baker tract offsite sewer\CAD plansheets\C-Const-Det1.dwg


This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.



ENTERED BY	PROJECT #
DESIGNED BY	DATE
CHECKED BY	REVISION
PROJ. ENGR.	
PATH	S:\Water Engineering\Engr\Design\Standard Details\wastewater details\Wastewater Detail Sheet 1-3.dwg



ENTERED BY	PROJECT #
DESIGNED BY	DATE
CHECKED BY	REVISION
PROJ. ENGR.	
PATH	S:\Water Engineering\Engr\Design\Standard Details\wastewater details\Wastewater Detail Sheet 1-3.dwg



STANDARD DETAILS

WASTEWATER DETAILS

DATE	SCALE
JUL. 2024	HOR 1"= N.T.S.
SHEET No.	VER 1"= N/A
6 OF 25	

CERTIFICATION:
THIS CITY OF DENTON STANDARD
DETAIL SHEET IS AUTHORIZED FOR
USE IN THIS PROJECT BY THE
ENGINEER WHOSE SEAL APPEARS
HEREON, AND WHO CERTIFIES THE
CONTENT OF THE DETAILS AND NOTES
HEREIN HAVE NOT BEEN ALTERED
AND ASSUMES RESPONSIBILITY FOR
APPROPRIATE USE OF THE
STANDARDS WITHIN THIS SHEET.

BAKER TRACT
OFFSITE SEWER
CITY OF DENTON, TEXAS

06/11/25
PROJECT NO.
063248015
SHEET NUMBER
C18.02

Kimley»Horn

© 2025 KIMLEY-HORN AND ASSOCIATES, INC.
6160 WARREN PARKWAY, SUITE 210, FRISCO, TX 75034
PHONE: 972-335-3580
WWW.KIMLEY-HORN.COM
TEXAS REGISTERED ENGINEERING FIRM F-928

STATE OF TEXAS
JOHN HALE
145833
LICENSED PROFESSIONAL ENGINEER
6/6/17/2025


SCALE
AS SHOWN
DESIGNED BY
JNC
DRAWN BY
JNC
CHECKED BY
JTH

CONSTRUCTION
DETAILS


REVISIONS

No.


DATE



S701



S702




5802




CITY OF
DENTON
ENGINEERING SERVICES

CERTIFICATION:
THIS CITY OF DENTON STANDARD
DETAIL SHEET IS AUTHORIZED FOR
USE IN THIS PROJECT BY THE
ENGINEER WHOSE SEAL APPEARS
HEREON, AND WHO CERTIFIES THE
CONTENT OF THE DETAILS AND NOTES
HEREIN HAVE NOT BEEN ALTERED
AND ASSUMES RESPONSIBILITY FOR
APPROPRIATE USE OF THE
STANDARDS WITHIN THIS SHEET.

**BAKER TRACT
OFFSITE SEWER
CITY OF DENTON, TEXAS**



U101



CITY OF DENTON
ENGINEERING SERVICES

DATE
JUL. 2024

SHEET No.
8 OF 25

CERTIFICATION:
THIS CITY OF DENTON STANDARD
DETAIL SHEET IS AUTHORIZED FOR USE
IN THIS PROJECT BY THE ENGINEER
WHOSE SEAL APPEARS HEREON, AND
WHO CERTIFIES THE CONTENT OF THE
DETAILS AND NOTES HEREIN HAVE NOT
BEEN ALTERED AND ASSUMES
RESPONSIBILITY FOR APPROPRIATE USE
OF THE STANDARDS WITHIN THIS SHEET

CERTIFICATION:
THIS CITY OF DENTON STANDARD
DETAIL SHEET IS AUTHORIZED FOR USE
IN THIS PROJECT BY THE ENGINEER
WHOSE SEAL APPEARS HEREON, AND
WHO CERTIFIES THE CONTENT OF THE
DETAILS AND NOTES HEREIN HAVE NOT
BEEN ALTERED AND ASSUMES
RESPONSIBILITY FOR APPROPRIATE USE
OF THE STANDARDS WITHIN THIS SHEET


DATE
06/11/25

PROJECT NO.
063248015

SHEET NUMBER
C18.04

CONSTRUCTION DETAILS


SCALE AS SHOWN	DESIGNED BY JNC	DRAWN BY JNC	CHECKED BY JTH
-------------------	--------------------	-----------------	-------------------



Kimley»»Horn
© 2025 KIMLEY-HORN AND ASSOCIATES, INC.
6160 WARREN PARKWAY, SUITE 210, FRISCO, TX 75034
PHONE: 972-335-3580
WWW.KIMLEY-HORN.COM
TEXAS REGISTERED ENGINEERING FIRM F-928


No.	REVISIONS	DATE	

Plotted By: Browning, Mason Date: June 11, 2025 08:42:49pm File Path: K:\Vri_civil\063248015 - Baker Tract Offsite Sewer\CAD\plansheets\C-Const-Detail.dwg This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.




TYPICAL SERVICE LINE LAYOUT

U206A




ALTERNATE SERVICE LINE LAYOUT
*(FOR LOTS LESS THAN 60' WIDE)

U206B




TRENCH DAM

U207



INSTALLATION IN STEEL CASING OR LINER PLATE
FOR PVC AND DIP


U208A



INSTALLATION IN STEEL CASING
FOR CONCRETE PRESSURE PIPE
BAR-WRAPPED STEEL CYLINDER TYPE

U208B

ENTERED BY	PROJECT #	
DESIGNED BY	DATE	REVISION
CHECKED BY		
PROJ. ENGR.		
PATH S:\Water Engineering\Engr\Design\Standard Details\water-wastewater shared drawings\Water-Wastewater Sht1-2.dwg		



STANDARD DETAILS

WATER/WASTEWATER SHARED DETAILS

DATE JUL. 2024	SCALE HOR 1"= N.T.S. VER 1"= N/A
SHEET No. 9 OF 25	

CERTIFICATION:
THIS CITY OF DENTON STANDARD
DETAIL SHEET IS AUTHORIZED FOR USE
IN THIS PROJECT BY THE ENGINEER
WHOSE SEAL APPEARS HEREON, AND
WHO CERTIFIES THE CONTENT OF THE
DETAILS AND NOTES HEREIN HAVE NOT
BEEN ALTERED AND ASSUMES
RESPONSIBILITY FOR APPROPRIATE USE
OF THE STANDARDS WITHIN THIS SHEET.

Kimley»Horn

© 2025 KIMLEY-HORN AND ASSOCIATES, INC.
6160 WARREN PARKWAY, SUITE 210, FRISCO, TX 75034
PHONE: 972-335-3580
WWW.KIMLEY-HORN.COM
TEXAS REGISTERED ENGINEERING FIRM F-928

STATE OF TEXAS
JOHN HALE
145833
LICENSED PROFESSIONAL ENGINEER
6/6/17/2025

SCALE
AS SHOWN
DESIGNED BY
JNC
DRAWN BY
JNC
CHECKED BY
JTH

CONSTRUCTION
DETAILS

BAKER TRACT
OFFSITE SEWER
CITY OF DENTON, TEXAS

DATE
06/11/25
PROJECT NO.
063248015
SHEET NUMBER
C18.05

REVISIONS

No.

DATE

EXHIBIT "C"
Estimated Costs and Proportionate Share

8

EXHIBIT C

6/13/2025

		Baker Tract			Harris Tract			City of Denton		Total Est Cost	
6-9-25 OPC public	Offsite Sewer	\$	484,522.02	9.95%	\$	131,478.34	2.70%	\$	4,253,567.65	87.35%	\$ 4,869,568.00
Sewer easement acquisition (Cole, John K Budget)		\$	35,710.55		\$	9,690.30		\$	313,499.15		\$ 358,900.00
	Kimley Design	\$	38,093.28		\$	10,336.87		\$	334,416.85		\$ 382,847.00
	Legal	\$	4,975.00		\$	1,350.00		\$	43,675.00		\$ 50,000.00
	<u>Closing Cost</u>	\$	<u>1,492.50</u>		\$	<u>405.00</u>		\$	<u>13,102.50</u>		\$ <u>15,000.00</u>
	Total	\$	564,793.34		\$	153,260.51		\$	4,958,261.15		\$ 5,676,315.00

* Sewer line cost based off of Kimley OPC dated 6/9/25

* See attached percent usage memo for Baker tract from Kimley

* Does not include ESA mitigation

NOTE: This exhibit is the preliminary budget numbers submitted to the city 6-13-25. The current cost for easement acquisition is \$400,000. The other numbers shown are based off of OPC provided by Kimley Horn and reviewed by the city. This will be updated once bids are received for sewer line and final easement is acquired.



EXHIBIT “D”
Incurred Costs

Baker Sewer Costs to Date
As of 11/19/25

Kimley Horn - last invoice through Sept 2025	303,987.11
Easement Purchase - John Karvouniaris	100,000.00
Easement Purchase - Mark Cole	300,000.00
<hr/>	
Total	703,987.11

EXHIBIT “E”
Reserved Capacity

EXHIBIT E



Building Name	Total SF	Required Parking	Provided Parking
Building 1 (Warehouse)	237,405	68	252
Building 1 (Office)	41,895	94	
Building 1 (Total)	279,300	162	
Building 2 (Warehouse)	729,300	209	497
Building 2 (Office)	128,700	286	
Building 2 (Total)	858,000	495	
Building 3 (Warehouse)	1,031,985	295	721
Building 3 (Office)	182,115	405	
Building 3 (Total)	1,214,100	700	
Building 4 (Warehouse)	103,870	30	371
Building 4 (Office)	18,330	41	
Building 4 (Total)	122,200	71	
Building 5 (Warehouse)	231,880	67	323
Building 5 (Office)	40,920	91	
Building 5 (Total)	272,800	158	
Building 6 (Warehouse)	231,880	67	324
Building 6 (Office)	40,920	91	
Building 6 (Total)	272,800	158	
Building 7 (Warehouse)	318,325	91	481
Building 7 (Office)	56,175	125	
Building 7 (Total)	374,500	216	
Building 8 (Warehouse)	48,640	14	140
Building 8 (Office)	12,160	28	
Building 8 (Total)	60,800	42	
Building 9 (Warehouse)	46,080	14	126
Building 9 (Office)	11,520	26	
Building 9 (Total)	57,600	40	
Building 10 (Warehouse)	46,080	14	127
Building 10 (Office)	11,520	26	
Building 10 (Total)	57,600	40	

Building	Wastewater Source	Applicable Unit	Total Building Area	Warehouse (65%)	Packaging Plant (15%)	Office (20%)	Warehouse 1/3500 SF Pop/Unit (Parking Req.)	Packaging Plant 1/1000 SF Pop/Unit (Parking Req.)	Office 1/450 SF Pop/Unit (Parking Req.)	Population	Sewage Design Flow Per Unit (gpd)*	ADF* (gpd)	ADF (gpm)	Peaking Factor	PDF (gpd)	PDF (gpm)
1	Industrial	SF	279,300	181,545	41,895	55,860	52	42	125	219	20	4,380	3	4	17,520	12.2
2	Industrial	SF	858,000	557,700	128,700	171,600	160	129	382	671	20	13,420	9	4	53,680	37.3
3	Industrial	SF	1,214,100	789,165	182,115	242,820	226	183	540	949	20	18,980	13	4	75,920	52.7
4	Industrial	SF	122,200	79,430	18,330	24,440	23	19	55	97	20	1,940	1	4	7,760	5.4
5	Industrial	SF	272,800	177,320	40,920	54,560	51	41	122	214	20	4,280	3	4	17,120	11.9
6	Industrial	SF	272,800	177,320	40,920	54,560	51	41	122	214	20	4,280	3	4	17,120	11.9
7	Industrial	SF	374,500	243,425	56,175	74,900	70	57	167	294	20	5,880	4	4	23,520	16.3
8	Industrial	SF	60,800	39,520	9,120	12,160	12	10	28	50	20	1,000	1	4	4,000	2.8
9	Industrial	SF	57,600	37,440	8,640	11,520	11	9	26	46	20	920	1	4	3,680	2.6
10	Industrial	SF	57,600	37,440	8,640	11,520	11	9	26	46	20	920	1	4	3,680	2.6
										2,800					224,000	155.6

*Design Flows and Peaking Factor from City of Denton Design Criteria Manual (Section 6.3.1)

Denton, Texas
October 2024

Kimley»Horn

6160 Warren Parkway, Suite 210
Frisco, Texas 75034
972-335-3580
State of Texas Registration No. F-928

NOTES:
1. THIS PLAN IS CONCEPTUAL IN NATURE AND HAS BEEN PRODUCED WITHOUT THE
BENEFIT OF A SURVEY OR CONTACT WITH THE CITY, COUNTY, ETC.
2. AERIAL IMAGE BY NEARMAP, COPYRIGHT 2023

DWG NAME:
LAST SAVED:

K:\P\ CIVIL\003248001 - BAKER TRACT - RM SQUARE\CAD\PRELIMINARY\EXHIBITS\PLANS\SHEETS\SITE PLAN.DWG
10/9/2024 2:31 PM