



PROPOSAL PREPARED FOR:

John Dillard  
City of Denton - Lake Lewisville Water  
Treatment Plant

PROJECT NAME:

City of Denton LLWTP - 2500 KVA Transformer  
Replacement

SHERMCO QUOTE NUMBER: SIQ-00010142-25

APPROVED BY: Lee Dawkins

May 14, 2025

**Dallas Service Center**

2425 E. Pioneer Dr., Irving, TX 75061  
Office (972) 793-5523





May 14, 2025

John Dillard  
City of Denton - Lake Lewisville Water Treatment Plant  
1701-B Spencer Road  
Denton, Texas, 76249

Re: City of Denton LLWTP - 2500 KVA Transformer Replacement  
SHERMCO Quote # SIQ-00010142-25

Shermco Industries is pleased to offer this proposal for the scope of work listed below:

**FIXED PRICE ..... \$147,500.00**

Payment terms net 30 days from the date of the invoice. Pricing does not include any applicable taxes, permits and licensing fees. All sales subject to Shermco Industries, Inc. standard terms and conditions dated 9-14-2023. All freight will be prepaid and added to the invoice.

#### **EQUIPMENT**

Qty: 1 ea. 3-Phase Padmount Transformer  
Remanufactured 2500 kVA 3-Ph Padmount Transformer  
High Voltage: 13200 GY 7620, 95 kV BIL  
Low Voltage: 2400 D, 30 kV BIL  
Taps: 13860, 13530, 13200, 12870, 12540  
HV Bushings: (3) 200A Wells & Inserts (dead front, radial feed)  
LV Bushings: (4) 2-Hole Spades (common H0/X0)  
Fluid: Mineral Oil  
Frequency: 60 Hz  
Temperature Rise: 65°C  
Cooling Class: ONAN  
Conductor: Al / Al  
Features & Accessories:  
Pressure Relief Valve

#### **WORKSCOPE**

Shermco will provide NETA certified technician(s) to remove existing 2500 KVA Transformer , Supply & test replacement transformer with (2) IR Windows & Dispose of existing Transformer

*\*NOTE: Optional testing is not included in the pricing listed above.*