

- EXISTING TREE CANOPY

CANOPY WITHIN ESA

ESA CANOPY TO BE REMOVED

ESA MITIGATION CANOPY

PROPOSED SITE CANOPY TO BE PROTECTED

DISTURBED ESA

MITIGATED ESA AREA
1. CONTOURS REPRESENT EXISTING GRADE

2. FIELD SURVEY WORK PROVIDED BY KAV SURVEY. WORK PERFORMED ON NOVEMBER 2016. PRELIMINARY AND SUBJECT TO CHANGE AS THE PROJECT DESIGN PROGRESSES. THE BASINS PROPOSED REPRESENT A DESIRE TO TREAT STORM WATER RUNOFF FROM THE DEVELOPED AREAS IDENTIFIED AS A2.1 AND A2.3.

3. THE PROPOSED MITIGATION CANOPY IS A PRELIMINARY DESIGN AND IS SUBJECT TO CHANGE AS THE PROJECT DESIGN PROGRESSES. THE BASINS PROPOSED REPRESENT A DESIRE TO TREAT STORM WATER RUNOFF FROM THE DEVELOPED AREAS IDENTIFIED AS A2.1 AND A2.3.

ESA TREE CANOPY TABLE		
	SF	AC
ESA Canopy Removal	10,087.29	0.23
ESA Mitigation Area Existing Tree Canopy	9,897.40	0.23
Mitigation Canopy Proposed	2,048.00	0.05
Total Mitigated Tree Canopy	11,945.40	0.27

